BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Roads and Drains at Bharathnagara , Sadiq Layout, Anjanadri Layout, Balance Roads and Surrounding Area in Ward No.06 Byatarayanapura Sub Division

MODIFIED ESTIMATE

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.01		Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed. the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Anam Enclave										
		Urdu School Road (W1589)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	40.3		Cum	1	10.30	0.90	0.90	0.90	0.90	8.34		
		Fathima Furniture Oppo. Road (W1579)										
		North to South										
		RHS										
0	9.8		Cum	1	9.80	0.90	0.90	0.90	0.90	7.94		
9.8	15		Cum	1	5.20	0.90	0.90	0.90	0.90	4.21		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	40.5		Cum	1	10.50	0.90	0.90	0.90	0.90	8.51		
		Fathima Furniture Beside Road (W1577)										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105	109.2		Cum	1	4.20	1.10	1.10	1.10	0.90	4.16		
		M.F Bike Zone Oppo. Road (W1569)										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	16.2		Cum	1	1.20	1.10	1.10	1.10	0.90	1.19		
		Chikkanna Layout										
		4th Cross Road (W1259)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
270	279.6		Cum	1	9.60	0.90	0.90	0.90	0.90	7.78		
		3rd Cross Road (W1257)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		

Scanned by CamScanner

90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
270	285		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
285	286.8		Cum	1	1.80	0.90	0.90	0.90	0.90	1.46		
		Sadique Layout										
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	38.8		Cum	1	8.80	0.90	0.90	0.90	0.90	7.13		
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	35		Cum	1	5.00	0.90	0.90	0.90	0.90	4.05		
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	70.8		Cum	1	10.80	0.90	0.90	0.90	0.90	8.75		
		4th Cross Road (W1555)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	75.5		Cum	1	15.50	0.90	0.90	0.90	0.90	12.56		
		5th Cross Road (W1559)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	29.5		Cum	1	14.50	0.90	0.90	0.90	0.90	11.75		
29.5	40		Cum	1	10.50	0.90	0.90	0.90	0.90	8.51		
40	55		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
55	70		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
70	75.5		Cum	1	5.50	0.90	0.90	0.90	0.90	4.46		
		6th Cross Road (W1563)										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105	115.7		Cum	1	10.70	1.10	1.10	1.10	0.90	10.59		
		Star Clinic Beside Road (W1513)										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	41		Cum	1	11.00	1.10	1.10	1.10	0.90	10.89		

Scanned by CamScanner

		Al Hadi Chicken Centre Oppo Road (W1521)										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	43.3		Cum	1	13.30	1.10	1.10	1.10	0.90	13.17		
		Masjid-E-Uqba Back Side										
		East to West										
		RHS										
0	12		Cum	1	12.00	0.90	0.90	0.90	0.90	9.72		
12	20	0	Cum	1	8.00	0.90	0.90	0.90	0.90	6.48		
20	25.4	Culvert										
25.4	32.8	0	Cum	1	7.40	0.90	0.90	0.90	0.90	5.99		
32.8	45		Cum	1	12.20	0.90	0.90	0.90	0.90	9.88		
45	53.9		Cum	1	8.90	0.90	0.90	0.90	0.90	7.21		
53.9	68.2	0	Cum	1	14.30	0.90	0.90	0.90	0.90	11.58		
68.2	74.8		Cum	1	6.60	0.90	0.90	0.90	0.90	5.35		
74.8	79.8	0	Cum	1	5.00	0.90	0.90	0.90	0.90	4.05		
79.8	90		Cum	1	10.20	0.90	0.90	0.90	0.90	8.26		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
105	113.5		Cum	1	8.50	0.90	0.90	0.90	0.90	6.89		
0	0	LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	73.3		Cum	1	13.30	1.10	1.10	1.10	0.90	13.17		
73.3	79.2	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
79.2	86	0	Cum	1	6.80	1.10	1.10	1.10	0.90	6.73		
86	100		Cum	1	14.00	1.10	1.10	1.10	0.90	13.86		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
115	125		Cum	1	10.00	1.10	1.10	1.10	0.90	9.90		
		Masjid-E-Uqba (W1493)										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	25.2		Cum	1	10.20	1.10	1.10	1.10	0.90	10.10		
		Masjid-E-Uqba (W1493)										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	25.5		Cum	1	10.50	1.10	1.10	1.10	0.90	10.40		
		W1038										
		LHS										
		West to East										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	76.8		Cum	1	1.80	1.10	1.10	1.10	0.90	1.78		
		Mount Hera English School Back Side (W1042)										
		LHS										
		West to East										
0	8		Cum	1	8.00	1.10	1.10	1.10	0.90	7.92		
8	17.7	0	Cum	1	9.70	1.10	1.10	1.10	0.90	9.60		
17.7	32.7		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
32.7	47.7		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
47.7	62.7		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
62.7	67.7		Cum	1	5.00	1.10	1.10	1.10	0.90	4.95		
		Mount Hera English School Road (W1515)										
		LHS										
0	12.3	0	Cum	1	12.30	1.10	1.10	1.10	0.90	12.18		
12.3	24.5		Cum	1	12.20	1.10	1.10	1.10	0.90	12.08		
24.5	31.4	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
31.4	46.4		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
46.4	56.7		Cum	1	10.30	1.10	1.10	1.10	0.90	10.20		

Scanned by CamScanner

56.7	63.1	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00	
		Amara Jyothi Layout Main Road									
		East to West									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	23.2	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
23.2	35.7		Cum	1	12.50	0.90	0.90	0.90	0.90	10.13	
35.7	47.8	0	Cum	1	12.10	0.90	0.90	0.90	0.90	9.80	
47.8	53.5	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
53.5	65		Cum	1	11.50	0.90	0.90	0.90	0.90	9.32	
65	78.4		Cum	1	13.40	0.90	0.90	0.90	0.90	10.85	
78.4	83.6	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
83.6	95		Cum	1	11.40	0.90	0.90	0.90	0.90	9.23	
95	109.5		Cum	1	14.50	0.90	0.90	0.90	0.90	11.75	
109.5	161	No Work	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
161	165.8	0	Cum	1	4.80	0.90	0.90	0.90	0.90	3.89	
165.8	174.5		Cum	1	8.70	0.90	0.90	0.90	0.90	7.05	
174.5	178.7	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
178.7	190		Cum	1	11.30	0.90	0.90	0.90	0.90	9.15	
190	205		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
205	220		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
220	229.5		Cum	1	9.50	0.90	0.90	0.90	0.90	7.70	
229.5	234.2	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
234.2	245		Cum	1	10.80	0.90	0.90	0.90	0.90	8.75	
245	258.8		Cum	1	13.80	0.90	0.90	0.90	0.90	11.18	
258.8	264.4	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
264.4	280		Cum	1	15.60	0.90	0.90	0.90	0.90	12.64	
280	284.6		Cum	1	4.60	0.90	0.90	0.90	0.90	3.73	
		Bharath Nagara									
		N R Bike Point Beside (W0782)									
		East to West									
		RHS									
0	6.6	0	Cum	1	6.60	0.90	0.90	0.90	0.90	5.35	
6.6	15		Cum	1	8.40	0.90	0.90	0.90	0.90	6.80	
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
60	75		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
75	90		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
105	115.5		Cum	1	10.50	0.90	0.90	0.90	0.90	8.51	
		LHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	24.9		Cum	1	9.90	0.90	0.90	0.90	0.90	8.02	
24.9	29.9	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
29.9	42		Cum	1	12.10	0.90	0.90	0.90	0.90	9.80	
42	55.6		Cum	1	13.60	0.90	0.90	0.90	0.90	11.02	
55.6	60.3	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
60.3	75		Cum	1	14.70	0.90	0.90	0.90	0.90	11.91	
75	85.4		Cum	1	10.40	0.90	0.90	0.90	0.90	8.42	
85.4	90.5	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
90.5	100.8		Cum	1	10.30	0.90	0.90	0.90	0.90	8.34	
100.8	115.5	0	Cum	1	14.70	0.90	0.90	0.90	0.90	11.91	
		Cross Road 1 (W1185)									
		North to South									
		RHS									
0	15	0	Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	20.5	0	Cum	1	5.50	0.90	0.90	0.90	0.90	4.46	
		Cross Road 2 (W1193)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	28		Cum	1	13.00	0.90	0.90	0.90	0.90	10.53	
		Cross Road 3 (W1197)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	27		Cum	1	12.00	0.90	0.90	0.90	0.90	9.72	

Scanned by CamScanner

		Cross Road 5 (W1183)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	35.5		Cum	1	5.50	0.90	0.90	0.90	0.90	4.46		
		R A Store Oppo. Road (W0966)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.90	7.70		
		Sameer Salon Road (W1425)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
120	130.2		Cum	1	10.20	0.90	0.90	0.90	0.90	8.26		
		M S Pharma Oppo. Road (W1441)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	50.5		Cum	1	5.50	0.90	0.90	0.90	0.90	4.46		
		Cross Road 1 (W0982)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	32.2		Cum	1	2.20	0.90	0.90	0.90	0.90	1.78		
		Cross Road 2 (W0978)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	28.7		Cum	1	13.70	0.90	0.90	0.90	0.90	11.10		
		P K Fruits Road (W1461)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	74.5		Cum	1	14.50	0.90	0.90	0.90	0.90	11.75		
		Bismillah Hotel Oppo. Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60	72.5		Cum	1	12.50	0.90	0.90	0.90	0.90	10.13		
		Trithwa Ashrama Road (W1435)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	21.8		Cum	1	6.80	1.10	1.10	1.10	0.90	6.73		
21.8	26.3	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
26.3	40		Cum	1	13.70	1.10	1.10	1.10	0.90	13.56		
40	50.9		Cum	1	10.90	1.10	1.10	1.10	0.90	10.79		
50.9	55.2	Culvert	Cum	1	0.00	1.20	1.20	1.20	0.90	0.00		
55.2	66.9		Cum	1	11.70	1.20	1.20	1.20	0.90	12.64		

Scanned by CamScanner

66.9	80		Cum	1	13.10	1.20	1.20	1.20	0.90	14.15		
80	95		Cum	1	15.00	1.20	1.20	1.20	0.90	16.20		
95	103		Cum	1	8.00	1.20	1.20	1.20	0.90	8.64		
		S K Creative Interiors Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90	100.5		Cum	1	10.50	1.10	1.10	1.10	0.90	10.40		
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90	93.5		Cum	1	3.50	1.10	1.10	1.10	0.90	3.47		
		Bharath Store (W1411)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	23.5		Cum	1	8.50	1.10	1.10	1.10	0.90	8.42		
23.5	25.5	No Work	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
25.5	40		Cum	1	14.50	1.10	1.10	1.10	0.90	14.36		
40	52.9		Cum	1	12.90	1.10	1.10	1.10	0.90	12.77		
52.9	60	No Work	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	88.3		Cum	1	13.30	1.10	1.10	1.10	0.90	13.17		
		Global Presenting Road (W1403)										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	84.6		Cum	1	9.60	1.10	1.10	1.10	0.90	9.50		
		Shalimar Products Road (W1397)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	80.5		Cum	1	5.50	1.10	1.10	1.10	0.90	5.45		
		R L Provision Store Road (W1387)										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75	76		Cum	1	1.00	1.10	1.10	1.10	0.90	0.99		
		Madeena Store Road (W0786)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		

Scanned by CamScanner

60	75		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
75	90		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
90	105		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
105	115.6		Cum	1	10.60	0.90	0.90	0.90	0.90	8.59	
115.6	130		Cum	1	14.40	1.10	1.10	1.10	0.90	14.26	
130	145		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
145	160		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
160	175		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
175	190		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
190	205		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
205	220		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
220	235		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
235	250		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
250	265		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
265	280		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
280	285.2		Cum	1	5.20	1.10	1.10	1.10	0.90	5.15	
		N R Bike Point Oppo Road									
		West to East									
		LHS									
0	11.8		Cum	1	11.80	1.10	1.10	1.10	0.90	11.68	
11.8	16	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00	
16	30		Cum	1	14.00	1.10	1.10	1.10	0.90	13.86	
30	40.9		Cum	1	10.90	1.10	1.10	1.10	0.90	10.79	
40.9	45	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00	
45	60		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
60	69.7		Cum	1	9.70	1.10	1.10	1.10	0.90	9.60	
69.7	74.8	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00	
74.8	90		Cum	1	15.20	1.10	1.10	1.10	0.90	15.05	
90	105		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
105	120		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85	
120	130.5		Cum	1	10.50	1.10	1.10	1.10	0.90	10.40	
		Anjanadri Layout									
		5th Main Road									
		East to West									
		LHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	30		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
30	45		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
45	60		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	26.5		Cum	1	11.50	0.90	0.90	0.90	0.90	9.32	
26.5	32.7	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00	
32.7	45		Cum	1	12.30	0.90	0.90	0.90	0.90	9.96	
45	57.9		Cum	1	12.90	0.90	0.90	0.90	0.90	10.45	
		Cross Road 1									
		South to North									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	25.1		Cum	1	10.10	0.90	0.90	0.90	0.90	8.18	
		LHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	21.5		Cum	1	6.50	0.90	0.90	0.90	0.90	5.27	
		Cross Road 2									
		South to North									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.90	7.70	
		LHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15	
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.90	7.70	
		For Culvert									
		Bharath Nagara									
		Madeena Store Road (W0786)									
			Cum	1	3.80	1.70	1.70	1.70	0.95	6.14	
		Masjid-E-Uqba Back Side									
			Cum	1	5.90	2.00	2.00	2.00	0.95	11.21	

Scanned by CamScanner

		N R Bike Point Beside (W0782)											
			Cum	1	7.20	1.40	1.40	1.40	0.95	9.58			
			Cum	1	7.30	1.40	1.40	1.40	0.95	9.71			
			Cum	1	5.60	1.40	1.40	1.40	0.95	7.45			
			Cum	1	5.00	1.40	1.40	1.40	0.95	6.65			
			Cum	1	5.00	1.40	1.40	1.40	0.95	6.65			
			Cum	1	4.70	1.40	1.40	1.40	0.95	6.25			
			Cum	1	5.10	1.40	1.40	1.40	0.95	6.78			
		Sameer Salon Road (W1425)											
			Cum	1	3.50	1.40	1.40	1.40	0.95	4.66			
			Cum	1	4.20	1.40	1.40	1.40	0.95	5.59			
		Bismillah Hotel Oppo Road											
			Cum	1	5.30	1.40	1.40	1.40	0.95	7.05			
		Trithwa Ashrama Road (W1435)											
			Cum	1	4.50	1.40	1.40	1.40	0.95	5.99			
			Cum	1	4.30	1.40	1.40	1.40	0.95	5.72			
		5th Main Road											
			Cum	1	6.30	1.40	1.40	1.40	0.95	8.38			
			Cum	1	6.20	1.40	1.40	1.40	0.95	8.25			
		W1038	Cum	1	6.90	1.30	1.30	1.30	0.95	8.52			
		Mount Hera English School Back	Cum	1	6.40	1.30	1.30	1.30	0.95	7.90			
		For SSM Culvert											
		Amara Jyothi Layout Main Road											
		2nd Cross Road											
			Cum	1	5.50	1.60	1.60	1.60	0.75	6.60			
		3rd Cross Road	Cum	1	6.10	1.60	1.60	1.60	0.75	7.32			
		4th Cross Road	Cum	1	6.90	1.60	1.60	1.60	0.75	8.28			
		6th Cross Road	Cum	1	4.40	1.60	1.60	1.60	0.75	5.28			
		7th Cross Road	Cum	1	6.20	1.60	1.60	1.60	0.75	7.44			
		8th Cross Road	Cum	1	5.75	1.60	1.60	1.60	0.75	6.90			
		For Desilt											
		W1515											
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50			
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50			
30	39.3		Cum	1	9.30	0.60	0.60	0.60	0.50	2.79			
									Total Executed Quantity	**3633.24**			
									Tender Quantity	**3374.84**			
									Quantity upto 125%	**3633.24**	**210.00**	**762981.00**

Item no.02 Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering complete as per specifications and as per the directions of the Engineer-in-charge of the work

		Drain PCC											
		Anam Enclave											
		Urdu School Road (W1589)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
30	40.3		Cum	1	10.30	0.90	0.90	0.90	0.15	1.39			
		Fathima Furniture Oppo. Road											
		North to South											
		RHS											
0	9.8		Cum	1	9.80	0.90	0.90	0.90	0.15	1.32			
9.8	15		Cum	1	5.20	0.90	0.90	0.90	0.15	0.70			
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
30	40.5		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42			
		Fathima Furniture Beside Road (W1577)											
		RHS											
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48			
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48			
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48			
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48			

Scanned by CamScanner

60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	109.2		Cum	1	4.20	1.10	1.10	1.10	0.15	0.69		
		M.F Bike Zone Oppo. Road										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	16.2		Cum	1	1.20	1.10	1.10	1.10	0.15	0.20		
		Chikkanna Layout										
		4th Cross Road (W1259)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270	279.6		Cum	1	9.60	0.90	0.90	0.90	0.15	1.30		
		3rd Cross Road (W1257)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270	285		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
285	286.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		Sadique Layout										
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	38.8		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	35		Cum	1	5.00	0.90	0.90	0.90	0.15	0.68		
		3rd Cross Road (W1543)										
		North to South										
		LHS										

Scanned by CamScanner

0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	70.8		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46		
		4th Cross Road (W1555)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75.5		Cum	1	15.50	0.90	0.90	0.90	0.15	2.09		
		5th Cross Road (W1559)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	29.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
29.5	40		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42		
40	55		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
55	70		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
70	75.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74		
		6th Cross Road (W1563)										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	115.7		Cum	1	10.70	1.10	1.10	1.10	0.15	1.77		
		Star Clinic Beside Road (W1513)										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	41		Cum	1	11.00	1.10	1.10	1.10	0.15	1.82		
		Al Hadi Chicken Centre Oppo. Road (W1521)										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	43.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
		Masjid-E-Uqba Back Side										
		East to West										
		RHS										
0	12		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
12	20		Cum	1	8.00	0.90	0.90	0.90	0.15	1.08		
20	25.4	**Culvert**										
25.4	32.8		Cum	1	7.40	0.90	0.90	0.90	0.15	1.00		
32.8	45		Cum	1	12.20	0.90	0.90	0.90	0.15	1.65		
45	53.9		Cum	1	8.90	0.90	0.90	0.90	0.15	1.20		
53.9	68.2		Cum	1	14.30	0.90	0.90	0.90	0.15	1.93		
68.2	74.8		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
74.8	79.8		Cum	1	5.00	0.90	0.90	0.90	0.15	0.68		
79.8	90		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	113.5		Cum	1	8.50	0.90	0.90	0.90	0.15	1.15		
0	0	**LHS**										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	73.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
73.3	79.2	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		

Scanned by CamScanner

79.2	86		Cum	1	6.80	1.10	1.10	1.10	0.15	1.12		
86	100		Cum	1	14.00	1.10	1.10	1.10	0.15	2.31		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	125		Cum	1	10.00	1.10	1.10	1.10	0.15	1.65		
		Masjid-E-Uqba (W1493)										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	25.2		Cum	1	10.20	1.10	1.10	1.10	0.15	1.68		
		Masjid-E-Uqba (W1493)										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	25.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		W1038										
		LHS										
		West to East										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	76.8		Cum	1	1.80	1.10	1.10	1.10	0.15	0.30		
		Mount Hera English School Back Side (W1042)										
		LHS										
		West to East										
0	8		Cum	1	8.00	1.10	1.10	1.10	0.15	1.32		
8	17.7		Cum	1	9.70	1.10	1.10	1.10	0.15	1.60		
17.7	32.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
32.7	47.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
47.7	62.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
62.7	67.7		Cum	1	5.00	1.10	1.10	1.10	0.15	0.83		
		Mount Hera English School Road (W1515)										
		LHS										
0	12.3		Cum	1	12.30	1.10	1.10	1.10	0.15	2.03		
12.3	24.5		Cum	1	12.20	1.10	1.10	1.10	0.15	2.01		
24.5	31.4	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
31.4	46.4		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
46.4	56.7		Cum	1	10.30	1.10	1.10	1.10	0.15	1.70		
56.7	63.1	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
		Amara Jyothi Layout Main Road (W0764)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.2	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
23.2	35.7		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
35.7	47.8		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63		
47.8	53.5	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
53.5	65		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
65	78.4		Cum	1	13.40	0.90	0.90	0.90	0.15	1.81		
78.4	83.6	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
83.6	95		Cum	1	11.40	0.90	0.90	0.90	0.15	1.54		
95	109.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
109.5	161	**No Work**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
161	165.8		Cum	1	4.80	0.90	0.90	0.90	0.15	0.65		
165.8	174.5		Cum	1	8.70	0.90	0.90	0.90	0.15	1.17		
174.5	178.7	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
178.7	190		Cum	1	11.30	0.90	0.90	0.90	0.15	1.53		
190	205		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
205	220		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
220	229.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
229.5	234.2	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
234.2	245		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46		
245	258.8		Cum	1	13.80	0.90	0.90	0.90	0.15	1.86		
258.8	264.4	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
264.4	280		Cum	1	15.60	0.90	0.90	0.90	0.15	2.11		
280	284.6		Cum	1	4.60	0.90	0.90	0.90	0.15	0.62		

Scanned by CamScanner

		Bharath Nagara											
		N.R Bike Point Beside (W0782)											
		East to West											
		RHS											
0	6.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89			
6.6	15		Cum	1	8.40	0.90	0.90	0.90	0.15	1.13			
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
105	115.5		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42			
		LHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	24.9		Cum	1	9.90	0.90	0.90	0.90	0.15	1.34			
24.9	29.9	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00			
29.9	42		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63			
42	55.6		Cum	1	13.60	0.90	0.90	0.90	0.15	1.84			
55.6	60.3	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00			
60.3	75		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98			
75	85.4		Cum	1	10.40	0.90	0.90	0.90	0.15	1.40			
85.4	90.5	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00			
90.5	100.8		Cum	1	10.30	0.90	0.90	0.90	0.15	1.39			
100.8	115.5		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98			
		Cross Road 1 (W1185)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	20.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74			
		Cross Road 2 (W1193)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	28		Cum	1	13.00	0.90	0.90	0.90	0.15	1.76			
		Cross Road 3 (W1197)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	27		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62			
		Cross Road 5 (W1183)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
30	35.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74			
		R A Store Oppo. Road (W0966)											
		East to West											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28			
		Sameer Salon Road (W1425)											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			
120	130.2		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38			
		M S Pharma Oppo. Road											
		North to South											
		RHS											
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03			

Scanned by CamScanner

15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	50.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74		
		Cross Road 1 (W0982)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	32.2		Cum	1	2.20	0.90	0.90	0.90	0.15	0.30		
		Cross Road 2 (W0978)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	28.7		Cum	1	13.70	0.90	0.90	0.90	0.15	1.85		
		P K Fruits Road (W1461)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	74.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
		Bismillah Hotel Oppo. Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	72.5		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
		Trithwa Ashrama Road (W1435)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	21.8		Cum	1	6.80	1.10	1.10	1.10	0.15	1.12		
21.8	26.3	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
26.3	40		Cum	1	13.70	1.10	1.10	1.10	0.15	2.26		
40	50.9		Cum	1	10.90	1.10	1.10	1.10	0.15	1.80		
50.9	55.2	**Culvert**	Cum	1	0.00	1.20	1.20	1.20	0.15	0.00		
55.2	66.9		Cum	1	11.70	1.20	1.20	1.20	0.15	2.11		
66.9	80		Cum	1	13.10	1.20	1.20	1.20	0.15	2.36		
80	95		Cum	1	15.00	1.20	1.20	1.20	0.15	2.70		
95	103		Cum	1	8.00	1.20	1.20	1.20	0.15	1.44		
		S K Creative Interiors Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	100.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	93.5		Cum	1	3.50	1.10	1.10	1.10	0.15	0.58		
		Bharath Store (W1411)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Scanned by CamScanner

15	23.5		Cum	1	8.50	1.10	1.10	1.10	0.15	1.40		
23.5	25.5	**No Work**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
25.5	40		Cum	1	14.50	1.10	1.10	1.10	0.15	2.39		
40	52.9		Cum	1	12.90	1.10	1.10	1.10	0.15	2.13		
52.9	60	**No Work**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	88.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
		Global Presenting Road (W1403)										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	84.6		Cum	1	9.60	1.10	1.10	1.10	0.15	1.58		
		Shalimar Products Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	80.5		Cum	1	5.50	1.10	1.10	1.10	0.15	0.91		
		R L Provision Store Road										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	76		Cum	1	1.00	1.10	1.10	1.10	0.15	0.17		
		Madeena Store Road (W0786)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	115.6		Cum	1	10.60	0.90	0.90	0.90	0.15	1.43		
115.6	130		Cum	1	14.40	1.10	1.10	1.10	0.15	2.38		
130	145		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
145	160		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
160	175		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
175	190		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
190	205		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
205	220		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
220	235		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
235	250		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
250	265		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
265	280		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
280	285.2		Cum	1	5.20	1.10	1.10	1.10	0.15	0.86		
		N R Bike Point Oppo. Road										
		West to East										
		LHS										
0	11.8		Cum	1	11.80	1.10	1.10	1.10	0.15	1.95		
11.8	16	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
16	30		Cum	1	14.00	1.10	1.10	1.10	0.15	2.31		
30	40.9		Cum	1	10.90	1.10	1.10	1.10	0.15	1.80		
40.9	45	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	69.7		Cum	1	9.70	1.10	1.10	1.10	0.15	1.60		
69.7	74.8	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
74.8	90		Cum	1	15.20	1.10	1.10	1.10	0.15	2.51		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Scanned by CamScanner

105	120		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120	130.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		Anjanadri Layout										
		5th Main Road										
		East to West										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	26.5		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
26.5	32.7	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
32.7	45		Cum	1	12.30	0.90	0.90	0.90	0.15	1.66		
45	57.9		Cum	1	12.90	0.90	0.90	0.90	0.15	1.74		
		Cross Road 1										
		South to North										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.1		Cum	1	10.10	0.90	0.90	0.90	0.15	1.36		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	21.5		Cum	1	6.50	0.90	0.90	0.90	0.15	0.88		
		Cross Road 2										
		South to North										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
		For Culvert										
		Bharath Nagara										
		Madeena Store Road (W0786)										
			Cum	1	3.80	1.70	1.70	1.70	0.15	0.97		
		Masjid-E-Uqba Back Side										
			Cum	1	5.90	2.00	2.00	2.00	0.15	1.77		
		N.R Bike Point Beside (W0782)										
			Cum	1	7.20	1.40	1.40	1.40	0.15	1.51		
			Cum	1	7.30	1.40	1.40	1.40	0.15	1.53		
			Cum	1	5.60	1.40	1.40	1.40	0.15	1.18		
			Cum	1	5.00	1.40	1.40	1.40	0.15	1.05		
			Cum	1	5.00	1.40	1.40	1.40	0.15	1.05		
			Cum	1	4.70	1.40	1.40	1.40	0.15	0.99		
			Cum	1	5.10	1.40	1.40	1.40	0.15	1.07		
		Sameer Salon Road (W1425)										
			Cum	1	3.50	1.40	1.40	1.40	0.15	0.74		
			Cum	1	4.20	1.40	1.40	1.40	0.15	0.88		
		Bismillah Hotel Oppo. Road										
			Cum	1	5.30	1.40	1.40	1.40	0.15	1.11		
		Trithwa Ashrama Road (W1435)										
			Cum	1	4.50	1.40	1.40	1.40	0.15	0.95		
			Cum	1	4.30	1.40	1.40	1.40	0.15	0.90		
		5th Main Road										
			Cum	1	6.30	1.40	1.40	1.40	0.15	1.32		
			Cum	1	6.20	1.40	1.40	1.40	0.15	1.30		
		W1038	Cum	1	6.90	1.30	1.30	1.30	0.15	1.35		
		Mount Hera English School	Cum	1	6.40	1.30	1.30	1.30	0.15	1.25		
		For Kerb										
		Amara Jyothi Layout Main Road (W0764)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		

Scanned by CamScanner

15	23 2	**Culvert**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
23 2	35 7		Cum	1	12 50	0 20	0 20	0 20	0 10	0 25		
35 7	47 8		Cum	1	12 10	0 20	0 20	0 20	0 10	0 24		
47 8	53 5	**Culvert**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
53 5	65		Cum	1	11 50	0 20	0 20	0 20	0 10	0 23		
65	78 4		Cum	1	13 40	0 20	0 20	0 20	0 10	0 27		
78 4	83 6	**Culvert**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
83 6	95		Cum	1	11 40	0 20	0 20	0 20	0 10	0 23		
95	109 5		Cum	1	14 50	0 20	0 20	0 20	0 10	0 29		
109 5	161	**No Work**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
161	165 8	**No Kerb**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
165 8	174 5		Cum	1	8 70	0 20	0 20	0 20	0 10	0 17		
174 5	178 7	**Culvert**	Cum	1	0 00	0 20	0 20	0 20	0 10	0 00		
178 7	190		Cum	1	11.30	0.20	0.20	0 20	0.10	0 23		
190	205		Cum	1	15.00	0 20	0.20	0.20	0.10	0 30		
205	220		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
220	229 5		Cum	1	9.50	0.20	0.20	0.20	0.10	0.19		
229 5	234 2	**Culvert**	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
234 2	245		Cum	1	10.80	0.20	0.20	0.20	0.10	0.22		
245	258 8		Cum	1	13.80	0.20	0.20	0.20	0.10	0.28		
258 8	264 4	**Culvert**	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
264 4	280		Cum	1	15.60	0.20	0.20	0.20	0.10	0.31		
280	284 6		Cum	1	4.60	0.20	0.20	0.20	0.10	0.09		
		Mount Hera English School Road (W1515)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
12 3	24 5		Cum	1	12.20	0.20	0.20	0.20	0.10	0.24		
24 5	31 4	**Culvert**	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
31 4	46 4		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
46 4	56 7		Cum	1	10.30	0.20	0.20	0.20	0.10	0.21		
56 7	63 1	**Culvert**	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
63 1	78 1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
78 1	93.1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
93.1	102.4		Cum	1	9.30	0.20	0.20	0.20	0.10	0.19		
		For SSM Culvert										
		Amara Jyothi Layout Main										
		2nd Cross Road										
			Cum	1	5.50	1.60	1.60	1.60	0.15	1.32		
		3rd Cross Road	Cum	1	6.10	1.60	1.60	1.60	0.15	1.46		
		4th Cross Road	Cum	1	6.90	1.60	1.60	1.60	0.15	1.66		
		6th Cross Road	Cum	1	4.40	1.60	1.60	1.60	0.15	1.06		
		7th Cross Road	Cum	1	6.20	1.60	1.60	1.60	0.15	1.49		
		8th Cross Road	Cum	1	5.75	1.60	1.60	1.60	0.15	1.38		
										Total Executed Quantity	**609.54**	
										Tender Quantity	**595.20**	
										Quantity upto 125%	**609.54**	**6000.00**	**3657222.00**
Item no.03		Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification and as per the directions of the Engineer-in-charge of the work											
		Bottom Raft										
		Anam Enclave										
		Urdu School Road (W1589)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	40 3		Cum	1	10.30	0.90	0.90	0.90	0.15	1.39		
		Fathima Furniture Oppo. Road										
		North to South										
		RHS										
0	9 8		Cum	1	9.80	0.90	0.90	0.90	0.15	1.32		
9 8	15		Cum	1	5.20	0 90	0 90	0.90	0.15	0.70		
15	30		Cum	1	15.00	0 90	0.90	0.90	0.15	2.03		
30	40 5		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42		

Scanned by CamScanner

		Fathima Furniture Beside Road (W1577)										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	109.2		Cum	1	4.20	1.10	1.10	1.10	0.15	0.69		
		M.F Bike Zone Oppo. Road										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	16.2		Cum	1	1.20	1.10	1.10	1.10	0.15	0.20		
		Chikkanna Layout										
		4th Cross Road (W1259)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270	279.6		Cum	1	9.60	0.90	0.90	0.90	0.15	1.30		
		3rd Cross Road (W1257)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	135		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135	150		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
150	165		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
165	180		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
180	195		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
195	210		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
210	225		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
225	240		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
240	255		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255	270		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270	285		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
285	286.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		Sadique Layout										
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Scanned by CamScanner

15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	38.8		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	35		Cum	1	5.00	0.90	0.90	0.90	0.15	0.68		
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	70.8		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46		
		4th Cross Road (W1555)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75.5		Cum	1	15.50	0.90	0.90	0.90	0.15	2.09		
		5th Cross Road (W1559)										
		South to North										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	29.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
29.5	40		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42		
40	55		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
55	70		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
70	75.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74		
		6th Cross Road (W1563)										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	115.7		Cum	1	10.70	1.10	1.10	1.10	0.15	1.77		
		Star Clinic Beside Road (W1513)										
		North to South										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	41		Cum	1	11.00	1.10	1.10	1.10	0.15	1.82		
		Al Hadi Chicken Centre Oppo.										
		South to North										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	43.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
		Masjid-E-Uqba Back Side										
		East to West										
		RHS										
0	12		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
12	20		Cum	1	8.00	0.90	0.90	0.90	0.15	1.08		
20	25.4	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
25.4	32.8		Cum	1	7.40	0.90	0.90	0.90	0.15	1.00		
32.8	45		Cum	1	12.20	0.90	0.90	0.90	0.15	1.65		
45	53.9		Cum	1	8.90	0.90	0.90	0.90	0.15	1.20		
53.9	68.2		Cum	1	14.30	0.90	0.90	0.90	0.15	1.93		

Scanned by CamScanner

68.2	74.8		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
74.8	79.8		Cum	1	5.00	0.90	0.90	0.90	0.15	0.68		
79.8	90		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	113.5		Cum	1	8.50	0.90	0.90	0.90	0.15	1.15		
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	73.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
73.3	79.2	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
79.2	86		Cum	1	6.80	1.10	1.10	1.10	0.15	1.12		
86	100		Cum	1	14.00	1.10	1.10	1.10	0.15	2.31		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	125		Cum	1	10.00	1.10	1.10	1.10	0.15	1.65		
		Masjid-E-Uqba (W1493)										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	25.2		Cum	1	10.20	1.10	1.10	1.10	0.15	1.68		
		Masjid-E-Uqba (W1493)										
		LHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	25.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		W1038										
		LHS										
		West to East										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	76.8		Cum	1	1.80	1.10	1.10	1.10	0.15	0.30		
		Mount Hera English School Back										
		LHS										
		West to East										
0	8		Cum	1	8.00	1.10	1.10	1.10	0.15	1.32		
8	17.7		Cum	1	9.70	1.10	1.10	1.10	0.15	1.60		
17.7	32.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
32.7	47.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
47.7	62.7		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
62.7	67.7		Cum	1	5.00	1.10	1.10	1.10	0.15	0.83		
		Mount Hera English School Road										
		LHS										
0	12.3		Cum	1	12.30	1.10	1.10	1.10	0.15	2.03		
12.3	24.5		Cum	1	12.20	1.10	1.10	1.10	0.15	2.01		
24.5	31.4	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
31.4	46.4		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
46.4	56.7		Cum	1	10.30	1.10	1.10	1.10	0.15	1.70		
56.7	63.1	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
		Amara Jyothi Layout Main										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.2	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
23.2	35.7		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
35.7	47.8		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63		
47.8	53.5	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
53.5	65		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
65	78.4		Cum	1	13.40	0.90	0.90	0.90	0.15	1.81		
78.4	83.6	**Culvert**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
83.6	95		Cum	1	11.40	0.90	0.90	0.90	0.15	1.54		
95	109.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
109.5	161	**No Work**	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
161	165.8		Cum	1	4.80	0.90	0.90	0.90	0.15	0.65		

Scanned by CamScanner

165.8	174.5		Cum	1	8.70	0.90	0.90	0.90	0.15	1.17	
174.5	178.7	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
178.7	190		Cum	1	11.30	0.90	0.90	0.90	0.15	1.53	
190	205		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
205	220		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
220	229.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28	
229.5	234.2	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
234.2	245		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46	
245	258.8		Cum	1	13.80	0.90	0.90	0.90	0.15	1.86	
258.8	264.4	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
264.4	280		Cum	1	15.60	0.90	0.90	0.90	0.15	2.11	
280	284.6		Cum	1	4.60	0.90	0.90	0.90	0.15	0.62	
		Bharath Nagara									
		N.R Bike Point Beside (W0782)									
		East to West									
		RHS									
0	6.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89	
6.6	15		Cum	1	8.40	0.90	0.90	0.90	0.15	1.13	
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
105	115.5		Cum	1	10.50	0.90	0.90	0.90	0.15	1.42	
		LHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	24.9		Cum	1	9.90	0.90	0.90	0.90	0.15	1.34	
24.9	29.9	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
29.9	42		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63	
42	55.6		Cum	1	13.60	0.90	0.90	0.90	0.15	1.84	
55.6	60.3	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
60.3	75		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98	
75	85.4		Cum	1	10.40	0.90	0.90	0.90	0.15	1.40	
85.4	90.5	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00	
90.5	100.8		Cum	1	10.30	0.90	0.90	0.90	0.15	1.39	
100.8	115.5		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98	
		Cross Road 1 (W1185)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	20.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74	
		Cross Road 2 (W1193)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	28		Cum	1	13.00	0.90	0.90	0.90	0.15	1.76	
		Cross Road 3 (W1197)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	27		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62	
		Cross Road 5 (W1183)									
		North to South									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
30	35.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74	
		R A Store Oppo. Road (W0966)									
		East to West									
		RHS									
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03	
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28	
		Sameer Salon Road (W1425)									

Scanned by CamScanner

		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	130.2		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
		M S Pharma Oppo. Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	50.5		Cum	1	5.50	0.90	0.90	0.90	0.15	0.74		
		Cross Road 1 (W0982)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	32.2		Cum	1	2.20	0.90	0.90	0.90	0.15	0.30		
		Cross Road 2 (W0978)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	28.7		Cum	1	13.70	0.90	0.90	0.90	0.15	1.85		
		P K Fruits Road (W1461)										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	74.5		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
		Bismillah Hotel Oppo. Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	72.5		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
		Trithwa Ashrama Road (W1435)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	21.8		Cum	1	6.80	1.10	1.10	1.10	0.15	1.12		
21.8	26.3	**Culvert**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
26.3	40		Cum	1	13.70	1.10	1.10	1.10	0.15	2.26		
40	50.9		Cum	1	10.90	1.10	1.10	1.10	0.15	1.80		
50.9	55.2	**Culvert**	Cum	1	0.00	1.20	1.20	1.20	0.15	0.00		
55.2	66.9		Cum	1	11.70	1.20	1.20	1.20	0.15	2.11		
66.9	80		Cum	1	13.10	1.20	1.20	1.20	0.15	2.36		
80	95		Cum	1	15.00	1.20	1.20	1.20	0.15	2.70		
95	103		Cum	1	8.00	1.20	1.20	1.20	0.15	1.44		
		S K Creative Interiors Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Scanned by CamScanner

60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	100.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	93.5		Cum	1	3.50	1.10	1.10	1.10	0.15	0.58		
		Bharath Store (W1411)										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	23.5		Cum	1	8.50	1.10	1.10	1.10	0.15	1.40		
23.5	25.5	**No Work**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
25.5	40		Cum	1	14.50	1.10	1.10	1.10	0.15	2.39		
40	52.9		Cum	1	12.90	1.10	1.10	1.10	0.15	2.13		
52.9	60	**No Work**	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	88.3		Cum	1	13.30	1.10	1.10	1.10	0.15	2.19		
		Global Presenting Road (W1403)										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	84.6		Cum	1	9.60	1.10	1.10	1.10	0.15	1.58		
		Shalimar Products Road										
		North to South										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	80.5		Cum	1	5.50	1.10	1.10	1.10	0.15	0.91		
		R L Provision Store Road										
		South to North										
		RHS										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	76		Cum	1	1.00	1.10	1.10	1.10	0.15	0.17		
		Madeena Store Road (W0786)										
		East to West										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	115.6		Cum	1	10.60	0.90	0.90	0.90	0.15	1.43		
115.6	130		Cum	1	14.40	1.10	1.10	1.10	0.15	2.38		
130	145		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
145	160		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
160	175		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
175	190		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Scanned by CamScanner

190	205		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
205	220		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
220	235		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
235	250		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
250	265		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
265	280		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
280	285.2		Cum	1	5.20	1.10	1.10	1.10	0.15	0.86		
		N R Bike Point Oppo. Road										
		West to East										
		LHS										
0	11.8		Cum	1	11.80	1.10	1.10	1.10	0.15	1.95		
11.8	16	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
16	30		Cum	1	14.00	1.10	1.10	1.10	0.15	2.31		
30	40.9		Cum	1	10.90	1.10	1.10	1.10	0.15	1.80		
40.9	45	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	69.7		Cum	1	9.70	1.10	1.10	1.10	0.15	1.60		
69.7	74.8	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
74.8	90		Cum	1	15.20	1.10	1.10	1.10	0.15	2.51		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	120		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120	130.5		Cum	1	10.50	1.10	1.10	1.10	0.15	1.73		
		Anjanadri Layout										
		5th Main Road										
		East to West										
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	26.5		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
26.5	32.7	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
32.7	45		Cum	1	12.30	0.90	0.90	0.90	0.15	1.66		
45	57.9		Cum	1	12.90	0.90	0.90	0.90	0.15	1.74		
		Cross Road 1										
		South to North										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.1		Cum	1	10.10	0.90	0.90	0.90	0.15	1.36		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	21.5		Cum	1	6.50	0.90	0.90	0.90	0.15	0.88		
		Cross Road 2										
		South to North										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	24.5		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
Measurements taken on												
		Side Wall										
		Anam Enclave										
		Urdu School Road (W1589)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	40.3		Cum	2	10.30	0.15	0.15	0.15	0.60	1.85		

Scanned by CamScanner

	Fathima Furniture Oppo Road (W1579)											
		North to South										
		RHS										
0	9 8		Cum	2	9 80	0 15	0 15	0 15	0 60	1 76		
9 8	15		Cum	2	5 20	0 15	0 15	0 15	0 60	0 94		
15	30		Cum	2	15 00	0 15	0 15	0 15	0 60	2 70		
30	40 5		Cum	2	10 50	0 15	0 15	0 15	0 60	1 89		
	Fathima Furniture Beside Road (W1577)											
		RHS										
0	15		Cum	2	15 00	0 15	0.15	0 15	0 60	2 70		
15	30		Cum	2	15 00	0 15	0 15	0 15	0 60	2 70		
30	45		Cum	2	15.00	0 15	0 15	0 15	0 60	2 70		
45	60		Cum	2	15 00	0 15	0 15	0 15	0 60	2 70		
60	75		Cum	2	15.00	0 15	0 15	0 15	0 60	2 70		
75	90		Cum	2	15 00	0 15	0 15	0 15	0 60	2 70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2 70		
105	109 2		Cum	2	4.20	0.15	0.15	0 15	0.60	0.76		
	M F Bike Zone Oppo. Road (W1569)											
		North to South										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	16 2		Cum	2	1.20	0.15	0.15	0.15	0.60	0.22		
		Chikkanna Layout										
		4th Cross Road (W1259)										
		South to North										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	135		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
135	150		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
150	165		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
165	180		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
180	195		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
195	210		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
210	225		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
225	240		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
240	255		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
255	270		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
270	279 6		Cum	2	9.60	0.15	0.15	0.15	0.60	1.73		
		3rd Cross Road (W1257)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	135		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
135	150		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
150	165		Cum	2	15.00	0.15	0.15	0.15	0 60	2 70		
165	180		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
180	195		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
195	210		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
210	225		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
225	240		Cum	2	15 00	0.15	0.15	0.15	0.60	2.70		
240	255		Cum	2	15 00	0.15	0 15	0.15	0.60	2.70		
255	270		Cum	2	15.00	0.15	0.15	0 15	0.60	2.70		
270	285		Cum	2	15.00	0 15	0 15	0.15	0.60	2.70		
285	286 8		Cum	2	1 80	0 15	0.15	0.15	0 60	0.32		

Scanned by CamScanner

		Sadique Layout										
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	38.8		Cum	2	8.80	0.15	0.15	0.15	0.60	1.58		
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	35		Cum	2	5.00	0.15	0.15	0.15	0.60	0.90		
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	70.8		Cum	2	10.80	0.15	0.15	0.15	0.60	1.94		
		4th Cross Road (W1555)										
		South to North										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75.5		Cum	2	15.50	0.15	0.15	0.15	0.60	2.79		
		5th Cross Road (W1559)										
		South to North										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	29.5		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
29.5	40		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
40	55		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
55	70		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
70	75.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
		6th Cross Road (W1563)										
		South to North										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	115.7		Cum	2	10.70	0.15	0.15	0.15	0.60	1.93		
		Star Clinic Beside Road (W1513)										
		North to South										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	41		Cum	2	11.00	0.15	0.15	0.15	0.60	1.98		
		Al Hadi Chicken Centre Oppo. Road (W1521)										
		South to North										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	43.3		Cum	2	13.30	0.15	0.15	0.15	0.60	2.39		
		Masjid-E-Uqba Back Side (W1036)										
		East to West										
		RHS										

Scanned by CamScanner

0	12		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		
12	20		Cum	2	8.00	0.15	0.15	0.15	0.60	1.44		
20	25.4	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
25.4	32.8		Cum	2	7.40	0.15	0.15	0.15	0.60	1.33		
32.8	45		Cum	2	12.20	0.15	0.15	0.15	0.60	2.20		
45	53.9		Cum	2	8.90	0.15	0.15	0.15	0.60	1.60		
53.9	68.2		Cum	2	14.30	0.15	0.15	0.15	0.60	2.57		
68.2	74.8		Cum	2	6.60	0.15	0.15	0.15	0.60	1.19		
74.8	79.8		Cum	2	5.00	0.15	0.15	0.15	0.60	0.90		
79.8	90		Cum	2	10.20	0.15	0.15	0.15	0.60	1.84		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	113.5		Cum	2	8.50	0.15	0.15	0.15	0.60	1.53		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	73.3		Cum	2	13.30	0.15	0.15	0.15	0.60	2.39		
73.3	79.2	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
79.2	86		Cum	2	6.80	0.15	0.15	0.15	0.60	1.22		
86	100		Cum	2	14.00	0.15	0.15	0.15	0.60	2.52		
100	115		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
115	125		Cum	2	10.00	0.15	0.15	0.15	0.60	1.80		
		Masjid-E-Uqba (W1493)										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	25.2		Cum	2	10.20	0.15	0.15	0.15	0.60	1.84		
		Masjid-E-Uqba (W1493)										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	25.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
		W1038										
		LHS										
		West to East										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	76.8		Cum	2	1.80	0.15	0.15	0.15	0.60	0.32		
		Mount Hera English School Back Side (W1042)										
		LHS										
		West to East										
0	8		Cum	2	8.00	0.15	0.15	0.15	0.60	1.44		
8	17.7		Cum	2	9.70	0.15	0.15	0.15	0.60	1.75		
17.7	32.7		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
32.7	47.7		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
47.7	62.7		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
62.7	67.7		Cum	2	5.00	0.15	0.15	0.15	0.60	0.90		
		Mount Hera English School Road (W1515)										
		LHS										
0	12.3		Cum	2	12.30	0.15	0.15	0.15	0.60	2.21		
12.3	24.5		Cum	2	12.20	0.15	0.15	0.15	0.60	2.20		
24.5	31.4	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
31.4	46.4		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
46.4	56.7		Cum	2	10.30	0.15	0.15	0.15	0.60	1.85		
56.7	63.1	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
		Amara Jyothi Layout Main Road (W0764)										
		East to West										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	23.2	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		

Scanned by CamScanner

23.2	35.7		Cum	2	12.50	0.15	0.15	0.15	0.60	2.25		
35.7	47.8		Cum	2	12.10	0.15	0.15	0.15	0.60	2.18		
47.8	53.5	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
53.5	65		Cum	2	11.50	0.15	0.15	0.15	0.60	2.07		
65	78.4		Cum	2	13.40	0.15	0.15	0.15	0.60	2.41		
78.4	83.6	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
83.6	95		Cum	2	11.40	0.15	0.15	0.15	0.60	2.05		
95	109.5		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
109.5	161	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
161	165.8		Cum	2	4.80	0.15	0.15	0.15	0.60	0.86		
165.8	174.5		Cum	2	8.70	0.15	0.15	0.15	0.60	1.57		
174.5	178.7	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
178.7	190		Cum	2	11.30	0.15	0.15	0.15	0.60	2.03		
190	205		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
205	220		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
220	229.5		Cum	2	9.50	0.15	0.15	0.15	0.60	1.71		
229.5	234.2	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
234.2	245		Cum	2	10.80	0.15	0.15	0.15	0.60	1.94		
245	258.8		Cum	2	13.80	0.15	0.15	0.15	0.60	2.48		
258.8	264.4	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
264.4	280		Cum	2	15.60	0.15	0.15	0.15	0.60	2.81		
280	284.6		Cum	2	4.60	0.15	0.15	0.15	0.60	0.83		
		Bharath Nagara										
		N R Bike Point Beside (W0782)										
		East to West										
		RHS										
0	6.6		Cum	2	6.60	0.15	0.15	0.15	0.60	1.19		
6.6	15		Cum	2	8.40	0.15	0.15	0.15	0.60	1.51		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	115.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	24.9		Cum	2	9.90	0.15	0.15	0.15	0.60	1.78		
24.9	29.9	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
29.9	42		Cum	2	12.10	0.15	0.15	0.15	0.60	2.18		
42	55.6		Cum	2	13.60	0.15	0.15	0.15	0.60	2.45		
55.6	60.3	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
60.3	75		Cum	2	14.70	0.15	0.15	0.15	0.60	2.65		
75	85.4		Cum	2	10.40	0.15	0.15	0.15	0.60	1.87		
85.4	90.5	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
90.5	100.8		Cum	2	10.30	0.15	0.15	0.15	0.60	1.85		
100.8	115.5		Cum	2	14.70	0.15	0.15	0.15	0.60	2.65		
		Cross Road 1 (W1185)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	20.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
		Cross Road 2 (W1193)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	28		Cum	2	13.00	0.15	0.15	0.15	0.60	2.34		
		Cross Road 3 (W1197)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	27		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		
		Cross Road 5 (W1183)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Scanned by CamScanner

15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	35.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
		R A Store Oppo. Road (W0966)										
		East to West										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	24.5		Cum	2	9.50	0.15	0.15	0.15	0.60	1.71		
		Sameer Salon Road (W1425)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	130.2		Cum	2	10.20	0.15	0.15	0.15	0.60	1.84		
		M S Pharma Oppo. Road (W1441)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	50.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
		Cross Road 1 (W0982)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	32.2		Cum	2	2.20	0.15	0.15	0.15	0.60	0.40		
		Cross Road 2 (W0978)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	28.7		Cum	2	13.70	0.15	0.15	0.15	0.60	2.47		
		P K Fruits Road (W1461)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	74.5		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
		Bismillah Hotel Oppo. Road (W1469)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	72.5		Cum	2	12.50	0.15	0.15	0.15	0.60	2.25		
		Trithwa Ashrama Road (W1435)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	21.8		Cum	2	6.80	0.15	0.15	0.15	0.60	1.22		
21.8	26.3	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
26.3	40		Cum	2	13.70	0.15	0.15	0.15	0.60	2.47		
40	50.9		Cum	2	10.90	0.15	0.15	0.15	0.60	1.96		
50.9	55.2	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
55.2	66.9		Cum	2	11.70	0.15	0.15	0.15	0.60	2.11		
66.9	80		Cum	2	13.10	0.15	0.15	0.15	0.60	2.36		

Scanned by CamScanner

80	95		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
95	103		Cum	2	8.00	0.15	0.15	0.15	0.60	1.44		
		S K Creative Interiors Road (W1419)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	100.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
		South to North										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	93.5		Cum	2	3.50	0.15	0.15	0.15	0.60	0.63		
		Bharath Store (W1411)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	23.5		Cum	2	8.50	0.15	0.15	0.15	0.60	1.53		
23.5	25.5	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
25.5	40		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
40	52.9		Cum	2	12.90	0.15	0.15	0.15	0.60	2.32		
52.9	60	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	88.3		Cum	2	13.30	0.15	0.15	0.15	0.60	2.39		
		Global Presenting Road (W1403)										
		South to North										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	84.6		Cum	2	9.60	0.15	0.15	0.15	0.60	1.73		
		Shalimar Products Road (W1397)										
		North to South										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	80.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
		R L Provision Store Road (W1387)										
		South to North										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	76		Cum	2	1.00	0.15	0.15	0.15	0.60	0.18		
		Madeena Store Road (W0786)										
		East to West										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Scanned by CamScanner

45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	115.6		Cum	2	10.60	0.15	0.15	0.15	0.60	1.91		
115.6	130		Cum	2	14.40	0.15	0.15	0.15	0.60	2.59		
130	145		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
145	160		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
160	175		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
175	190		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
190	205		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
205	220		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
220	235		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
235	250		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
250	265		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
265	280		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
280	285.2		Cum	2	5.20	0.15	0.15	0.15	0.60	0.94		
		N R Bike Point Oppo. Road (W0782)										
		West to East										
		LHS										
0	11.8		Cum	2	11.80	0.15	0.15	0.15	0.60	2.12		
11.8	16	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
16	30		Cum	2	14.00	0.15	0.15	0.15	0.60	2.52		
30	40.9		Cum	2	10.90	0.15	0.15	0.15	0.60	1.96		
40.9	45	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	69.7		Cum	2	9.70	0.15	0.15	0.15	0.60	1.75		
69.7	74.8	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
74.8	90		Cum	2	15.20	0.15	0.15	0.15	0.60	2.74		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	130.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
		Anjanadri Layout										
		5th Main Road										
		East to West										
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	26.5		Cum	2	11.50	0.15	0.15	0.15	0.60	2.07		
26.5	32.7	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
32.7	45		Cum	2	12.30	0.15	0.15	0.15	0.60	2.21		
45	57.9		Cum	2	12.90	0.15	0.15	0.15	0.60	2.32		
		Cross Road 1										
		South to North										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	25.1		Cum	2	10.10	0.15	0.15	0.15	0.60	1.82		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	21.5		Cum	2	6.50	0.15	0.15	0.15	0.60	1.17		
		Cross Road 2										
		South to North										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	24.5		Cum	2	9.50	0.15	0.15	0.15	0.60	1.71		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	24.5		Cum	2	9.50	0.15	0.15	0.15	0.60	1.71		
									Sub Total	1276.22		
		Culvert										
		Bottom Raft										

Scanned by CamScanner

		Bharath Nagara									
		Madeena Store Road (W0786)									
			Cum	1	3.80	1.70	1.70	1.70	0.20	1.29	
		Masjid-E-Uqba Back Side (W1036)									
			Cum	1	5.90	2.00	2.00	2.00	0.20	2.36	
		N.R Bike Point Beside (W0782)									
			Cum	1	7.20	1.40	1.40	1.40	0.20	2.02	
			Cum	1	7.30	1.40	1.40	1.40	0.20	2.04	
			Cum	1	5.60	1.40	1.40	1.40	0.20	1.57	
			Cum	1	5.00	1.40	1.40	1.40	0.20	1.40	
			Cum	1	5.00	1.40	1.40	1.40	0.20	1.40	
			Cum	1	4.70	1.40	1.40	1.40	0.20	1.32	
			Cum	1	5.10	1.40	1.40	1.40	0.20	1.43	
		Sameer Salon Road (W1425)									
			Cum	1	3.50	1.40	1.40	1.40	0.20	0.98	
			Cum	1	4.20	1.40	1.40	1.40	0.20	1.18	
		Bismillah Hotel Oppo. Road (W1469)									
			Cum	1	5.30	1.40	1.40	1.40	0.20	1.48	
		Trithwa Ashrama Road (W1435)									
			Cum	1	4.50	1.40	1.40	1.40	0.20	1.26	
			Cum	1	4.30	1.40	1.40	1.40	0.20	1.20	
		5th Main Road									
			Cum	1	6.30	1.40	1.40	1.40	0.20	1.76	
			Cum	1	6.20	1.40	1.40	1.40	0.20	1.74	
		W1038	Cum	1	6.90	1.30	1.30	1.30	0.20	1.79	
		Mount Hera English School Back Side (W	Cum	1	6.40	1.30	1.30	1.30	0.20	1.66	
		Side Wall									
		Bottom Raft									
		Bharath Nagara									
		Madeena Store Road (W0786)									
			Cum	2	3.80	0.23	0.23	0.23	0.60	1.05	
		Masjid-E-Uqba Back Side (W1036)									
			Cum	2	5.90	0.23	0.23	0.23	0.60	1.63	
		N.R Bike Point Beside (W0782)									
			Cum	2	7.20	0.23	0.23	0.23	0.60	1.99	
			Cum	2	7.30	0.23	0.23	0.23	0.60	2.01	
			Cum	2	5.60	0.23	0.23	0.23	0.60	1.55	
			Cum	2	5.00	0.23	0.23	0.23	0.60	1.38	
			Cum	2	5.00	0.23	0.23	0.23	0.60	1.38	
			Cum	2	4.70	0.23	0.23	0.23	0.60	1.30	
			Cum	2	5.10	0.23	0.23	0.23	0.60	1.41	
		Sameer Salon Road (W1425)									
			Cum	2	3.50	0.23	0.23	0.23	0.60	0.97	
			Cum	2	4.20	0.23	0.23	0.23	0.60	1.16	
		Bismillah Hotel Oppo. Road (W1469)									
			Cum	2	5.30	0.23	0.23	0.23	0.60	1.46	
		Trithwa Ashrama Road (W1435)									
			Cum	2	4.50	0.23	0.23	0.23	0.60	1.24	
			Cum	2	4.30	0.23	0.23	0.23	0.60	1.19	
		5th Main Road									
			Cum	2	6.30	0.23	0.23	0.23	0.60	1.74	
			Cum	2	6.20	0.23	0.23	0.23	0.60	1.71	
		W1038	Cum	2	6.90	0.23	0.23	0.23	0.60	1.90	
		Mount Hera English School Back Side (W	Cum	2	6.40	0.23	0.23	0.23	0.60	1.77	
									Sub Total		54.71
		For Culvert Ramp									
		Bharath Nagara									
		Madeena Store Road (W0786)									
			Cum	2	3.80	0.50	0.50	0.50	0.15	0.57	
		Masjid-E-Uqba Back Side (W1036)									
			Cum	2	5.90	0.50	0.50	0.50	0.15	0.89	
		N.R Bike Point Beside (W0782)									
			Cum	2	7.20	0.50	0.50	0.50	0.15	1.08	

Scanned by CamScanner

			Cum	2	7.30	0.50	0.50	0.50	0.15	1.10				
			Cum	2	5.60	0.50	0.50	0.50	0.15	0.84				
			Cum	2	5.00	0.50	0.50	0.50	0.15	0.75				
			Cum	2	5.00	0.50	0.50	0.50	0.15	0.75				
			Cum	2	4.70	0.50	0.50	0.50	0.15	0.71				
			Cum	2	5.10	0.50	0.50	0.50	0.15	0.77				
		Sameer Salon Road (W1425)												
			Cum	2	3.50	0.50	0.50	0.50	0.15	0.53				
			Cum	2	4.20	0.50	0.50	0.50	0.15	0.63				
		Bismillah Hotel Oppo. Road (W1469)												
			Cum	2	5.30	0.50	0.50	0.50	0.15	0.80				
		Trithwa Ashrama Road (W1435)												
			Cum	2	4.50	0.50	0.50	0.50	0.15	0.68				
			Cum	2	4.30	0.50	0.50	0.50	0.15	0.65				
		5th Main Road												
			Cum	2	6.30	0.50	0.50	0.50	0.15	0.95				
			Cum	2	6.20	0.45	0.45	0.45	0.15	0.84				
									Sub Total	12.49				
		For SSM Culvert												
		Bed Concrete												
		Amara Jyothi Layout Main Road (W0764)												
		2nd Cross Road												
			Cum	1	5.50	0.60	0.60	0.60	0.15	0.50				
		3rd Cross Road	Cum	1	6.10	0.60	0.60	0.60	0.15	0.55				
		4th Cross Road	Cum	1	6.90	0.60	0.60	0.60	0.15	0.62				
		6th Cross Road	Cum	1	4.40	0.60	0.60	0.60	0.15	0.40				
		7th Cross Road	Cum	1	6.20	0.60	0.60	0.60	0.15	0.56				
		8th Cross Road	Cum	1	5.75	0.60	0.60	0.60	0.15	0.52				
		Copping Concrete												
		Amara Jyothi Layout Main Road (W0764)												
		2nd Cross Road												
			Cum	2	5.50	0.45	0.45	0.45	0.10	0.50				
		3rd Cross Road	Cum	2	6.10	0.45	0.45	0.45	0.10	0.55				
		4th Cross Road	Cum	2	6.90	0.45	0.45	0.45	0.10	0.62				
		6th Cross Road	Cum	2	4.40	0.45	0.45	0.45	0.10	0.40				
		7th Cross Road	Cum	2	6.20	0.45	0.45	0.45	0.10	0.56				
		8th Cross Road	Cum	2	5.75	0.45	0.45	0.45	0.10	0.52				
									Sub Total	6.27				
									Total Executed Quantity	1349.70				
									Tender Quantity	1326.69				
									Quantity upto 125%	1349.70	8000.00	10797606.00		
Item no.04		Providing T M T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work												
		For Drain	Tonne		1276.22			0.08		95.72				
		For Culvert	Tonne		54.71			0.10		5.20				
									Total Executed Qty	100.91				
									Tender Quantity	99.30				
									Quantity upto 125%	100.91	93000.00	9385044.00		
Item no.05		Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work, curing, including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete and as per the directions of the Engineer-in-charge of the work												
		Anam Enclave												
		Urdu School Road (W1589)												
		North to South												
		RHS												
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25				
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25				

Scanned by CamScanner

30	40.3		Sqm	1	10.30	0.75	0.75	0.75		7.73		
		Fathima Furniture Oppo. Road (W1579)										
		North to South										
		RHS										
0	9.8		Sqm	1	9.80	0.75	0.75	0.75		7.35		
9.8	15		Sqm	1	5.20	0.75	0.75	0.75		3.90		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	40.5		Sqm	1	10.50	0.75	0.75	0.75		7.88		
		Fathima Furniture Beside Road										
		RHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90	105		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105	109.2		Sqm	1	4.20	0.90	0.90	0.90		3.78		
		M.F Bike Zone Oppo. Road										
		North to South										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	16.2		Sqm	1	1.20	0.90	0.90	0.90		1.08		
		Chikkanna Layout										
		4th Cross Road (W1259)										
		South to North										
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	120		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120	135		Sqm	1	15.00	0.75	0.75	0.75		11.25		
135	150		Sqm	1	15.00	0.75	0.75	0.75		11.25		
150	165		Sqm	1	15.00	0.75	0.75	0.75		11.25		
165	180		Sqm	1	15.00	0.75	0.75	0.75		11.25		
180	195		Sqm	1	15.00	0.75	0.75	0.75		11.25		
195	210		Sqm	1	15.00	0.75	0.75	0.75		11.25		
210	225		Sqm	1	15.00	0.75	0.75	0.75		11.25		
225	240		Sqm	1	15.00	0.75	0.75	0.75		11.25		
240	255		Sqm	1	15.00	0.75	0.75	0.75		11.25		
255	270		Sqm	1	15.00	0.75	0.75	0.75		11.25		
270	279.6		Sqm	1	9.60	0.75	0.75	0.75		7.20		
		3rd Cross Road (W1257)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	120		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120	135		Sqm	1	15.00	0.75	0.75	0.75		11.25		
135	150		Sqm	1	15.00	0.75	0.75	0.75		11.25		
150	165		Sqm	1	15.00	0.75	0.75	0.75		11.25		
165	180		Sqm	1	15.00	0.75	0.75	0.75		11.25		
180	195		Sqm	1	15.00	0.75	0.75	0.75		11.25		
195	210		Sqm	1	15.00	0.75	0.75	0.75		11.25		
210	225		Sqm	1	15.00	0.75	0.75	0.75		11.25		
225	240		Sqm	1	15.00	0.75	0.75	0.75		11.25		
240	255		Sqm	1	15.00	0.75	0.75	0.75		11.25		
255	270		Sqm	1	15.00	0.75	0.75	0.75		11.25		

Scanned by CamScanner

270	285		Sqm	1	15.00	0.75	0.75	0.75		11.25		
285	286.8		Sqm	1	1.80	0.75	0.75	0.75		1.35		
		Sadique Layout										
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	38.8		Sqm	1	8.80	0.75	0.75	0.75		6.60		
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	35		Sqm	1	5.00	0.75	0.75	0.75		3.75		
		3rd Cross Road (W1543)										
		North to South										
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	70.8		Sqm	1	10.80	0.75	0.75	0.75		8.10		
		4th Cross Road (W1555)										
		South to North										
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75.5		Sqm	1	15.50	0.75	0.75	0.75		11.63		
		5th Cross Road (W1559)										
		South to North										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	29.5		Sqm	1	14.50	0.90	0.90	0.90		13.05		
29.5	40		Sqm	1	10.50	0.75	0.75	0.75		7.88		
40	55		Sqm	1	15.00	0.75	0.75	0.75		11.25		
55	70		Sqm	1	15.00	0.75	0.75	0.75		11.25		
70	75.5		Sqm	1	5.50	0.75	0.75	0.75		4.13		
		6th Cross Road (W1563)										
		South to North										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90	105		Sqm	1	10.70	0.90	0.90	0.90		9.63		
105	115.7											
		Star Clinic Beside Road (W1513)										
		North to South										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	41		Sqm	1	11.00	0.90	0.90	0.90		9.90		
		Al Hadi Chicken Centre Oppo.										
		South to North										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	43.3		Sqm	1	13.30	0.90	0.90	0.90		11.97		
		Masjid-E-Uqba Back Side										

Scanned by CamScanner

		East to West										
		RHS										
0	12		Sqm	1	12.00	0.75	0.75	0.75		9.00		
12	20	**Old BS Slab**	Sqm	0	0.00	0.75	0.75	0.75		0.00		
20	25.4	**Culvert**	Sqm	1	0.00	0.75	0.75	0.75		0.00		
25.4	32.8	**Old BS Slab**	Sqm	0	0.00	0.00	0.00	0.00		0.00		
32.8	45		Sqm	1	12.20	0.75	0.75	0.75		9.15		
45	53.9		Sqm	1	8.90	0.75	0.75	0.75		6.68		
53.9	68.2	**Old BS Slab**	Sqm	0	0.00	0.75	0.75	0.75		0.00		
68.2	74.8		Sqm	1	6.60	0.75	0.75	0.75		4.95		
74.8	79.8	**Old BS Slab**	Sqm	0	0.00	0.75	0.75	0.75		0.00		
79.8	90		Sqm	1	10.20	0.75	0.75	0.75		7.65		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	113.5		Sqm	1	8.50	0.75	0.75	0.75		6.38		
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	73.3		Sqm	1	13.30	0.90	0.90	0.90		11.97		
73.3	79.2	**Culvert**	Sqm	1	0.00	0.90	0.90	0.90		0.00		
79.2	86	**Old BS Slab**	Sqm	1	0.00	0.90	0.90	0.90		0.00		
86	100		Sqm	1	14.00	0.90	0.90	0.90		12.60		
100	115		Sqm	1	15.00	0.90	0.90	0.90		13.50		
115	125		Sqm	1	10.00	0.90	0.90	0.90		9.00		
		Masjid-E-Uqba (W1493)										
		North to South										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	25.2		Sqm	1	10.20	0.90	0.90	0.90		9.18		
		Masjid-E-Uqba (W1493)										
		LHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	25.5		Sqm	1	10.50	0.90	0.90	0.90		9.45		
		W1038										
		LHS										
		West to East										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	76.8		Sqm	1	1.80	0.90	0.90	0.90		1.62		
		Mount Hera English School Back										
		LHS										
		West to East										
0	8		Sqm	1	8.00	0.90	0.90	0.90		7.20		
8	17.7	BS Slab	Sqm	1	0.00	0.00	0.00	0.00		0.00		
17.7	32.7		Sqm	1	15.00	0.90	0.90	0.90		13.50		
32.7	47.7		Sqm	1	15.00	0.90	0.90	0.90		13.50		
47.7	62.7		Sqm	1	15.00	0.90	0.90	0.90		13.50		
62.7	67.7		Sqm	1	5.00	0.90	0.90	0.90		4.50		
		Mount Hera English School Road (W1515)										
		LHS										
0	12.3	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
12.3	24.5		Sqm	1	12.20	0.90	0.90	0.90		10.98		
24.5	31.4	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
31.4	46.4		Sqm	1	15.00	0.90	0.90	0.90		13.50		
46.4	56.7		Sqm	1	10.30	0.90	0.90	0.90		9.27		
56.7	63.1	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Amara Jyothi Layout Main										
		East to West										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	23.2	**Culvert**	Sqm	0	0.00	0.75	0.75	0.75		0.00		

Scanned by CamScanner

23.2	35.7		Sqm	1	12.50	0.75	0.75	0.75	9.38		
35.7	47.8	Old BS Slab	Sqm	0	0.00	0.75	0.75	0.75	0.00		
47.8	53.5	Culvert	Sqm	1	0.00	0.75	0.75	0.75	0.00		
53.5	65		Sqm	1	11.50	0.75	0.75	0.75	8.63		
65	78.4		Sqm	1	13.40	0.75	0.75	0.75	10.05		
78.4	83.6	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
83.6	95		Sqm	1	11.40	0.75	0.75	0.75	8.55		
95	109.5		Sqm	1	14.50	0.75	0.75	0.75	10.88		
109.5	161	No Work	Sqm	0	0.00	0.75	0.75	0.75	0.00		
161	165.8	Old BS Slab	Sqm	0	0.00	0.75	0.75	0.75	0.00		
165.8	174.5		Sqm	1	8.70	0.75	0.75	0.75	6.52		
174.5	178.7	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
178.7	190		Sqm	1	11.30	0.75	0.75	0.75	8.48		
190	205		Sqm	1	15.00	0.75	0.75	0.75	11.25		
205	220		Sqm	1	15.00	0.75	0.75	0.75	11.25		
220	229.5		Sqm	1	9.50	0.75	0.75	0.75	7.13		
229.5	234.2	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
234.2	245		Sqm	1	10.80	0.75	0.75	0.75	8.10		
245	258.8		Sqm	1	13.80	0.75	0.75	0.75	10.35		
258.8	264.4	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
264.4	280		Sqm	1	15.60	0.75	0.75	0.75	11.70		
280	284.6		Sqm	1	4.60	0.75	0.75	0.75	3.45		
		Bharath Nagara									
		N.R Bike Point Beside (W0782)									
		East to West									
		RHS									
0	8.6	Old BS Slab	Sqm	0	0.00	0.75	0.75	0.75	0.00		
8.6	15		Sqm	1	8.40	0.75	0.75	0.75	6.30		
15	30		Sqm	1	15.00	0.75	0.75	0.75	11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75	11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75	11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75	11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75	11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75	11.25		
105	115.5		Sqm	1	10.50	0.75	0.75	0.75	7.88		
		LHS									
0	15		Sqm	1	15.00	0.75	0.75	0.75	11.25		
15	24.9		Sqm	1	9.90	0.75	0.75	0.75	7.43		
24.9	29.9	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
29.9	42		Sqm	1	12.10	0.75	0.75	0.75	9.08		
42	55.6		Sqm	1	13.60	0.75	0.75	0.75	10.20		
55.6	60.3	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
60.3	75		Sqm	1	14.70	0.75	0.75	0.75	11.03		
75	85.4		Sqm	1	10.40	0.75	0.75	0.75	7.80		
85.4	90.5	Culvert	Sqm	0	0.00	0.75	0.75	0.75	0.00		
90.5	100.8		Sqm	1	10.30	0.75	0.75	0.75	7.73		
100.8	115.5	Old BS Slab	Sqm	1	0.00	0.75	0.75	0.75	0.00		
		Cross Road 1 (W1185)									
		North to South									
		RHS									
0	15	Old BS Slab	Sqm	0	0.00	0.75	0.75	0.75	0.00		
15	20.5	Old BS Slab	Sqm	0	0.00	0.75	0.75	0.75	0.00		
		Cross Road 2 (W1193)									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.75	0.75	0.75	11.25		
15	28		Sqm	1	13.00	0.75	0.75	0.75	9.75		
		Cross Road 3 (W1197)									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.75	0.75	0.75	11.25		
15	27		Sqm	1	12.00	0.75	0.75	0.75	9.00		
		Cross Road 5 (W1183)									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.75	0.75	0.75	11.25		

Scanned by CamScanner

15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	35.5		Sqm	1	5.50	0.75	0.75	0.75		4.13		
		R A Store Oppo. Road (W0966)										
		East to West										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	24.5		Sqm	1	9.50	0.75	0.75	0.75		7.13		
		Sameer Salon Road (W1425)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	120		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120	130.2		Sqm	1	10.20	0.75	0.75	0.75		7.65		
		M S Pharma Oppo. Road										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	50.5		Sqm	1	5.50	0.75	0.75	0.75		4.13		
		Cross Road 1 (W0982)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	32.2		Sqm	1	2.20	0.75	0.75	0.75		1.65		
		Cross Road 2 (W0978)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	28.7		Sqm	1	13.70	0.75	0.75	0.75		10.28		
		P K Fruits Road (W1461)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	74.5		Sqm	1	14.50	0.75	0.75	0.75		10.88		
		Bismillah Hotel Oppo. Road										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	72.5		Sqm	1	12.50	0.75	0.75	0.75		9.38		
		Trithwa Ashrama Road (W1435)										
		North to South										
		RHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	21.8		Sqm	1	6.80	0.90	0.90	0.90		6.12		
21.8	26.3	**Culvert**	Sqm	1	0.00	0.90	0.90	0.90		0.00		
26.3	40		Sqm	1	13.70	0.90	0.90	0.90		12.33		
40	50.9		Sqm	1	10.90	0.90	0.90	0.90		9.81		
50.9	55.2	**Culvert**	Sqm	1	0.00	1.20	1.20	1.20		0.00		
55.2	66.9		Sqm	1	11.70	1.20	1.20	1.20		14.04		
66.9	80		Sqm	1	13.10	1.20	1.20	1.20		15.72		

Scanned by CamScanner

80	95		Sqm	1	15.00	1.20	1.20	1.20	18.00		
95	103		Sqm	1	8.00	1.20	1.20	1.20	9.60		
		S K Creative Interiors Road									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90	13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90	13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90	13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90	13.50		
90	100.5		Sqm	1	10.50	0.90	0.90	0.90	9.45		
		South to North									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90	13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90	13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90	13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90	13.50		
90	93.5		Sqm	1	3.50	0.90	0.90	0.90	3.15		
		Bharath Store (W1411)									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	23.5		Sqm	1	8.50	0.90	0.90	0.90	7.65		
23.5	25.5	No Work	Sqm	1	0.00	0.90	0.90	0.90	0.00		
25.5	40		Sqm	1	14.50	0.90	0.90	0.90	13.05		
40	52.9		Sqm	1	12.90	0.90	0.90	0.90	11.61		
52.9	60	No Work	Sqm	1	0.00	0.90	0.90	0.90	0.00		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	88.3		Sqm	1	13.30	0.90	0.90	0.90	11.97		
		Global Presenting Road (W1403)									
		South to North									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90	13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90	13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90	13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	84.6		Sqm	1	9.60	0.90	0.90	0.90	8.64		
		Shalimar Products Road									
		North to South									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90	13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90	13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90	13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	80.5		Sqm	1	5.50	0.90	0.90	0.90	4.95		
		R L Provision Store Road									
		South to North									
		RHS									
0	15		Sqm	1	15.00	0.90	0.90	0.90	13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90	13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90	13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90	13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90	13.50		
75	76		Sqm	1	1.00	0.90	0.90	0.90	0.90		
		Madeena Store Road (W0786)									
		East to West									
		RHS									
0	15		Sqm	1	15.00	0.75	0.75	0.75	11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75	11.25		

Scanned by CamScanner

30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	115.6		Sqm	1	10.60	0.75	0.75	0.75		7.95		
115.6	130		Sqm	1	14.40	0.90	0.90	0.90		12.96		
130	145		Sqm	1	15.00	0.90	0.90	0.90		13.50		
145	160		Sqm	1	15.00	0.90	0.90	0.90		13.50		
160	175		Sqm	1	15.00	0.90	0.90	0.90		13.50		
175	190		Sqm	1	15.00	0.90	0.90	0.90		13.50		
190	205		Sqm	1	15.00	0.90	0.90	0.90		13.50		
205	220		Sqm	1	15.00	0.90	0.90	0.90		13.50		
220	235		Sqm	1	15.00	0.90	0.90	0.90		13.50		
235	250		Sqm	1	15.00	0.90	0.90	0.90		13.50		
250	265		Sqm	1	15.00	0.90	0.90	0.90		13.50		
265	280		Sqm	1	15.00	0.90	0.90	0.90		13.50		
280	285.2		Sqm	1	5.20	0.90	0.90	0.90		4.68		
		N R Bike Point Oppo. Road										
		West to East										
		LHS										
0	11.8		Sqm	1	11.80	0.90	0.90	0.90		10.62		
11.8	16	**Culvert**										
16	30		Sqm	1	14.00	0.90	0.90	0.90		12.60		
30	40.9		Sqm	1	10.90	0.90	0.90	0.90		9.81		
40.9	45	**Culvert**										
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	69.7		Sqm	1	9.70	0.90	0.90	0.90		8.73		
69.7	74.8	**Culvert**										
74.8	90		Sqm	1	15.20	0.90	0.90	0.90		13.68		
90	105		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105	120		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120	130.5		Sqm	1	10.50	0.90	0.90	0.90		9.45		
		Anjanadri Layout										
		5th Main Road										
		East to West										
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	26.5		Sqm	1	11.50	0.75	0.75	0.75		8.63		
26.5	32.7	**Culvert**	Sqm	1	0.00	0.75	0.75	0.75		0.00		
32.7	45		Sqm	1	12.30	0.75	0.75	0.75		9.23		
45	57.9		Sqm	1	12.90	0.75	0.75	0.75		9.68		
		Cross Road 1										
		South to North										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	25.1		Sqm	1	10.10	0.75	0.75	0.75		7.58		
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	21.5		Sqm	1	6.50	0.75	0.75	0.75		4.88		
		Cross Road 2										
		South to North										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	24.5		Sqm	1	9.50	0.75	0.75	0.75		7.13		
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	24.5		Sqm	1	9.50	0.75	0.75	0.75		7.13		
		Missing Cover Slab	Sqm	12	0.90	0.60	0.60	0.60		6.48		

Scanned by CamScanner

										Total Executed Quantity	**3090.71**		
										Tender Quantity	**2936.40**		
										Quantity upto 125%	**3090.71**	**2000.00**	**6181410.00**
Item no.06		Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1 2 4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete and as per the directions of the Engineer-in-charge of the work										
		Bharath Nagara										
		Madeena Store Road (W0786)										
			Sqm	1	3 80	1 50	1 50	1 50		5 70		
		Masjid-E-Uqba Back Side										
			Sqm	1	5 90	1 80	1 80	1 80		10 62		
		N.R Bike Point Beside (W0782)										
			Sqm	1	7 20	1 20	1 20	1 20		8 64		
			Sqm	1	7 30	1 20	1 20	1 20		8 76		
			Sqm	1	5.60	1 20	1 20	1 20		6 72		
			Sqm	1	5.00	1 20	1 20	1 20		6.00		
			Sqm	1	5.00	1.20	1.20	1.20		6.00		
			Sqm	1	4.70	1.20	1.20	1.20		5.64		
			Sqm	1	5.10	1.20	1.20	1.20		6.12		
		Sameer Salon Road (W1425)										
			Sqm	1	3.50	1.20	1.20	1.20		4.20		
			Sqm	1	4.20	1.20	1.20	1.20		5.04		
		Bismillah Hotel Oppo. Road										
			Sqm	1	5.30	1.20	1.20	1.20		6.36		
		Trithwa Ashrama Road (W1435)										
			Sqm	1	4.50	1.20	1.20	1.20		5.40		
			Sqm	1	4.30	1.20	1.20	1.20		5.16		
		5th Main Road										
			Sqm	1	6.30	1.20	1.20	1.20		7.56		
			Sqm	1	6.20	1.20	1.20	1.20		7.44		
		W1038	Sqm	1	6.90	1.20	1.20	1.20		8.28		
		Mount Hera English School	Sqm	1	6.40	1.20	1.20	1.20		7.68		
		Amara Jyothi Layout Main 2nd Cross Road										
			Sqm	1	5.50	1.50	1.50	1.50		8.25		
		3rd Cross Road	Sqm	1	6.10	1.50	1.50	1.50		9.15		
		4th Cross Road	Sqm	1	6.90	1.50	1.50	1.50		10.35		
		6th Cross Road	Sqm	1	4.40	1.50	1.50	1.50		6.60		
		7th Cross Road	Sqm	1	6.20	1.50	1.50	1.50		9.30		
		8th Cross Road	Sqm	1	5.75	1.50	1.50	1.50		8.63		
										Total Executed Quantity	**173.60**	**5500.00**	**954773.00**
										Tender Quantity	**177.12**		
Item no.07		Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. and as per the directions of the Engineer-in-charge of the work										
		Amara Jyothi Layout Main Road (W0764)										
		East to West										
		RHS										
0	15		m	1	15.00					15.00		
15	23 2	**Culvert**	m	1	0.00					0.00		
23 2	35 7		m	1	12.50					12.50		
35 7	47 8		m	1	12.10					12.10		
47 8	53 5	**Culvert**	m	1	0.00					0.00		
53 5	65		m	1	11.50					11.50		
65	78 4		m	1	13.40					13.40		
78 4	83 6	**Culvert**	m	1	0.00					0.00		
83 6	95		m	1	11 40					11.40		
95	109 5		m	1	14.50					14.50		
109 5	161	**No Work**	m	1	0.00					0.00		
161	165 8	**No Kerb**	m	1	0.00					0.00		
165 8	174 5		m	1	8 70					8.70		
174 5	178 7	**Culvert**	m	1	0 00					0.00		
178 7	190		m	1	11 30					11.30		

Scanned by CamScanner

190	205		m	1	15.00					15.00			
205	220		m	1	15.00					15.00			
220	229.5		m	1	9.50					9.50			
229.5	234.2	**Culvert**	m	1	0.00					0.00			
234.2	245		m	1	10.80					10.80			
245	258.8		m	1	13.80					13.80			
258.8	264.4	**Culvert**	m	1	0.00					0.00			
264.4	280		m	1	15.60					15.60			
280	284.6		m	1	4.60					4.60			
		Mount Hera English School Road (W1515)											
		LHS											
0	15		m	1	15.00					15.00			
12.3	24.5		m	1	12.20					12.20			
24.5	31.4	Culvert	m	1	0.00					0.00			
31.4	46.4		m	1	15.00					15.00			
46.4	56.7		m	1	10.30					10.30			
56.7	63.1	Culvert	m	1	0.00					0.00			
63.1	78.1		m	1	15.00					15.00			
78.1	93.1		m	1	15.00					15.00			
93.1	102.4		m	1	9.30					9.30			
			m						**Total Length**	**286.50**			
			Nos		**Total Length/0.45**					**637.00**			
									Total Executed Quantity	**637.00**	**450.00**	**286650.00**	
									Tender Quantity	**2566.00**			

Item no.08		Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour Complete as per specifications and directions of the Engineer in charge.											
		Amara Jyothi Layout Main Road (W0764)											
		East to West											
		RHS											
0	15		Sqm	1	15.00				0.40	6.00			
15	23.2	Culvert	Sqm	1	0.00				0.40	0.00			
23.2	35.7		Sqm	1	12.50				0.40	5.00			
35.7	47.8		Sqm	1	12.10				0.40	4.84			
47.8	53.5	Culvert	Sqm	1	0.00				0.40	0.00			
53.5	65		Sqm	1	11.50				0.40	4.60			
65	78.4		Sqm	1	13.40				0.40	5.36			
78.4	83.6	Culvert	Sqm	1	0.00				0.40	0.00			
83.6	95		Sqm	1	11.40				0.40	4.56			
95	109.5		Sqm	1	14.50				0.40	5.80			
109.5	161	No Work	Sqm	1	0.00				0.40	0.00			
161	165.8	No Kerb	Sqm	1	0.00				0.40	0.00			
165.8	174.5		Sqm	1	8.70				0.40	3.48			
174.5	178.7	Culvert	Sqm	1	0.00				0.40	0.00			
178.7	190		Sqm	1	11.30				0.40	4.52			
190	205		Sqm	1	15.00				0.40	6.00			
205	220		Sqm	1	15.00				0.40	6.00			
220	229.5		Sqm	1	9.50				0.40	3.80			
229.5	234.2	Culvert	Sqm	1	0.00				0.40	0.00			
234.2	245		Sqm	1	10.80				0.40	4.32			
245	258.8		Sqm	1	13.80				0.40	5.52			
258.8	264.4	Culvert	Sqm	1	0.00				0.40	0.00			
264.4	280		Sqm	1	15.60				0.40	6.24			
280	284.6		Sqm	1	4.60				0.40	1.84			
		Mount Hera English School Road (W1515)											
		LHS											
0	15		Sqm	1	15.00				0.40	6.00			
12.3	24.5		Sqm	1	12.20				0.40	4.88			
24.5	31.4	Culvert	Sqm	1	0.00				0.40	0.00			
31.4	46.4		Sqm	1	15.00				0.40	6.00			
46.4	56.7		Sqm	1	10.30				0.40	4.12			
56.7	63.1	Culvert	Sqm	1	0.00				0.40	0.00			
63.1	78.1		Sqm	1	15.00				0.40	6.00			
78.1	93.1		Sqm	1	15.00				0.40	6.00			
93.1	102.4		Sqm	1	9.30				0.40	3.72			
									Total Executed Quantity	**114.60**	**100.00**	**11460.00**	
									Tender Quantity	**461.80**			

Scanned by CamScanner

Item no.09		Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications and as per the directions of the Engineer-in-charge of the work									
		Sadique Layout									
		Fathima Furniture Oppo Road									
		South to North									
0	9.8		Cum	1	9.80	4.95	4.70	4.83	0.45	21.28	
9.8	15		Cum	1	5.20	5.60	5.35	5.48	0.45	12.81	
15	30		Cum	1	15.00	5.35	5.45	5.40	0.45	36.45	
30	38.9		Cum	1	8.90	5.45	5.50	5.48	0.45	21.93	
		Cross Road 1 (W1062)									
		East to West									
0	15		Cum	1	15.00	6.40	6.45	6.43	0.45	43.37	
15	29.5		Cum	1	14.50	6.45	6.30	6.38	0.45	41.60	
		Cross Road 2 (W1060)									
		East to West									
0	15		Cum	1	15.00	6.10	6.30	6.20	0.45	41.85	
15	30		Cum	1	15.00	6.30	5.70	6.00	0.45	40.50	
30	37.8		Cum	1	7.80	5.70	5.60	5.65	0.45	19.83	
		3rd Cross Road (W1543)									
		North to South									
0	15		Cum	1	15.00	6.25	5.80	6.03	0.45	40.67	
15	30		Cum	1	15.00	5.80	6.00	5.90	0.45	39.83	
30	35		Cum	1	5.00	6.00	6.00	6.00	0.45	13.50	
35	38.8		Cum	1	3.80	6.80	6.80	6.80	0.45	11.63	
0	5.3		Cum	1	5.30	5.30	5.40	5.35	0.45	12.76	
5.3	15		Cum	1	9.70	4.40	5.30	4.85	0.45	21.17	
15	30		Cum	1	15.00	5.30	5.75	5.53	0.45	37.29	
30	45		Cum	1	15.00	5.75	5.30	5.53	0.45	37.29	
45	60		Cum	1	15.00	5.30	4.70	5.00	0.45	33.75	
60	75		Cum	1	15.00	4.70	4.40	4.55	0.45	30.71	
75	76.1		Cum	1	1.10	4.40	4.40	4.40	0.45	2.18	
		4th Cross Road (W1555)									
		South to North									
0	15		Cum	1	15.00	4.30	4.45	4.38	0.45	29.53	
15	30		Cum	1	15.00	4.45	4.50	4.48	0.45	30.21	
30	33.8		Cum	1	3.80	4.50	4.35	4.43	0.45	7.57	
33.8	37.2		Cum	1	3.40	5.00	5.00	5.00	0.45	7.65	
37.2	45		Cum	1	7.80	4.20	4.65	4.43	0.45	15.53	
45	60		Cum	1	15.00	4.65	4.65	4.65	0.45	31.39	
60	65.2		Cum	1	5.20	4.65	4.50	4.58	0.45	10.71	
65.2	74.5		Cum	1	9.30	3.75	4.05	3.90	0.45	16.32	
		5th Cross Road (W1559)									
		South to North									
0	12.5		Cum	1	12.50	3.40	3.90	3.65	0.45	20.53	
12.5	19.8		Cum	1	7.30	4.80	4.50	4.65	0.45	15.28	
19.8	26.5		Cum	1	6.70	5.20	5.40	5.30	0.45	15.98	
26.5	35		Cum	1	8.50	4.75	4.35	4.55	0.45	17.40	
35	50		Cum	1	15.00	4.35	3.50	3.93	0.45	26.49	
50	65		Cum	1	15.00	3.50	3.50	3.50	0.45	23.63	
65	75.5		Cum	1	10.50	3.50	2.55	3.03	0.45	14.29	
		5th A Cross Road (W1559)									
		North to South									
0	10.5		Cum	1	10.50	5.20	6.00	5.60	0.45	26.46	
10.5	20		Cum	1	9.50	2.80	2.70	2.75	0.45	11.76	
		Royal Fabricators Road (W171)									
		North to South									
0	15		Cum	1	15.00	5.50	5.95	5.73	0.45	38.64	
15	30		Cum	1	15.00	5.95	6.00	5.98	0.45	40.33	
30	41.3		Cum	1	11.30	6.00	4.90	5.45	0.45	27.71	
		Star Clinic Beside Road (W1513)									
		North to South									
0	15		Cum	1	15.00	5.00	4.80	4.90	0.45	33.08	
15	30		Cum	1	15.00	4.80	5.00	4.90	0.45	33.08	
30	41		Cum	1	11.00	5.00	4.15	4.58	0.45	22.65	

Scanned by CamScanner

		Al Hadi Chicken Centre Oppo Road (W1521)										
		South to North										
0	15		Cum	1	15.00	4.45	4.90	4.68	0.45	31.56		
15	30		Cum	1	15.00	4.90	5.05	4.98	0.45	33.58		
30	43		Cum	1	13.00	5.05	5.40	5.23	0.45	30.57		
		Bharath Nagara N R Bike Point Beside (W0782)										
		East to West										
0	15		Cum	1	15.00	5.15	5.30	5.23	0.45	35.27		
15	30		Cum	1	15.00	5.30	5.20	5.25	0.45	35.44		
30	45		Cum	1	15.00	5.20	5.30	5.25	0.45	35.44		
45	60		Cum	1	15.00	5.30	5.30	5.30	0.45	35.78		
60	75		Cum	1	15.00	5.30	5.40	5.35	0.45	36.11		
75	90		Cum	1	15.00	5.40	5.30	5.35	0.45	36.11		
90	105		Cum	1	15.00	5.30	5.30	5.30	0.45	35.78		
105	120		Cum	1	15.00	5.30	5.10	5.20	0.45	35.10		
120	121		Cum	1	1.00	5.10	5.10	5.10	0.45	2.30		
121	127		Cum	1	6.00	6.10	6.10	6.10	0.45	16.47		
		Cross Road 1 (W1185)										
		North to South										
0	15		Cum	1	15.00	5.30	5.30	5.30	0.45	35.78		
15	20.5		Cum	1	5.50	5.30	5.30	5.30	0.45	13.12		
20.5	24.5		Cum	1	4.00	2.50	2.50	2.50	0.45	4.50		
		Cross Road 2 (W1193)										
		North to South										
0	15		Cum	1	15.00	5.35	5.40	5.38	0.45	36.28		
15	28		Cum	1	13.00	5.40	4.80	5.10	0.45	29.84		
		Cross Road 3 (W1197)										
		North to South										
0	15		Cum	1	15.00	4.50	5.15	4.83	0.45	32.57		
15	18.6		Cum	1	3.60	5.15	5.15	5.15	0.45	8.34		
18.6	23.5		Cum	1	4.90	3.40	3.40	3.40	0.45	7.50		
23.5	27		Cum	1	3.50	5.15	5.10	5.13	0.45	8.07		
		Cross Road 4 (W1201)										
		North to South										
0	8.8		Cum	1	8.80	5.95	6.00	5.98	0.45	23.66		
8.8	15		Cum	1	6.20	4.30	5.10	4.70	0.45	13.11		
15	27.3		Cum	1	12.30	5.10	4.90	5.00	0.45	27.68		
		Cross Road 5 (W1183)										
		North to South										
0	15		Cum	1	15.00	5.10	5.00	5.05	0.45	34.09		
15	30		Cum	1	15.00	5.00	5.00	5.00	0.45	33.75		
30	34		Cum	1	4.00	5.00	4.90	4.95	0.45	8.91		
		R A Store Oppo Road (W0966)										
		East to West										
0	15		Cum	1	15.00	3.60	3.80	3.70	0.45	24.98		
15	24.5		Cum	1	9.50	3.80	3.90	3.85	0.45	16.46		
		Sameer Salon Road (W1425)										
		South to North										
0	4.2		Cum	1	4.20	3.60	3.60	3.60	0.45	6.80		
4.2	15		Cum	1	10.80	2.60	3.30	2.95	0.45	14.34		
15	30		Cum	1	15.00	3.30	3.60	3.45	0.45	23.29		
30	45		Cum	1	15.00	3.60	3.70	3.65	0.45	24.64		
45	60		Cum	1	15.00	3.70	3.80	3.75	0.45	25.31		
60	62.2		Cum	1	2.20	3.80	3.80	3.80	0.45	3.76		
62.2	63.4	Culvert	Cum	1	0.00	3.80	5.30	4.55	0.45	0.00		
63.4	67		Cum	1	3.60	3.80	3.80	3.80	0.45	6.16		
67	80		Cum	1	13.00	3.80	4.00	3.90	0.45	22.82		
80	95		Cum	1	15.00	4.00	3.90	3.95	0.45	26.66		
95	110		Cum	1	15.00	3.90	3.70	3.80	0.45	25.65		
110	125		Cum	1	15.00	3.70	3.90	3.80	0.45	25.65		
125	129		Cum	1	4.00	3.90	3.90	3.90	0.45	7.02		
		M S Pharma Oppo Road (W1441)										
		North to South										
0	15		Cum	1	15.00	3.80	3.40	3.60	0.45	24.30		

Scanned by CamScanner

15	30		Cum	1	15.00	3.40	3.80	3.60	0.45	24.30		
30	45		Cum	1	15.00	3.80	3.80	3.80	0.45	25.65		
45	53.1		Cum	1	8.10	3.80	3.80	3.80	0.45	13.85		
		Cross Road 1 (W0982)										
		East to West										
0	15		Cum	1	15.00	3.70	3.60	3.65	0.45	24.64		
15	30		Cum	1	15.00	3.60	3.60	3.60	0.45	24.30		
30	42.9		Cum	1	12.90	3.60	3.80	3.70	0.45	21.48		
		Cross Road 2 (W0978)										
		East to West										
0	15		Cum	1	15.00	3.40	3.40	3.40	0.45	22.95		
15	23.1		Cum	1	8.10	3.40	3.40	3.40	0.45	12.39		
23.1	28.7		Cum	1	5.60	1.90	1.90	1.90	0.45	4.79		
		Inspire Public School Oppo. Road (W0990)										
		West to East										
0	15		Cum	1	15.00	3.90	4.60	4.25	0.45	28.69		
15	20		Cum	1	5.00	4.60	4.85	4.73	0.45	10.63		
		Cross Road 4 (W0984)										
		East to West										
0	15		Cum	1	15.00	4.80	4.90	4.85	0.45	32.74		
15	19.5		Cum	1	4.50	4.90	5.00	4.95	0.45	10.02		
		Cross Road 3 (W0984)										
		West to East										
0	15		Cum	1	15.00	4.35	4.20	4.28	0.45	28.86		
15	24.9		Cum	1	9.90	4.20	4.20	4.20	0.45	18.71		
		Cross Road 2 (W0980)										
		East to West										
0	13.9		Cum	1	13.90	4.50	4.50	4.50	0.45	28.15		
13.9	18.6		Cum	1	4.70	4.00	4.00	4.00	0.45	8.46		
18.6	20.3		Cum	1	1.70	2.60	2.60	2.60	0.45	1.99		
20.3	25.4		Cum	1	5.10	3.30	3.30	3.30	0.45	7.57		
		Cross Road 1 (W0980)										
		West to East										
0	15		Cum	1	15.00	4.90	4.90	4.90	0.45	33.08		
15	24.1		Cum	1	9.10	4.90	4.90	4.90	0.45	20.07		
		Masjid-E-Uqba Road (W1483)										
		North to South										
0	8		Cum	1	8.00	5.00	4.30	4.65	0.45	16.74		
8	20		Cum	1	12.00	3.65	3.70	3.68	0.45	19.85		
20	30.5		Cum	1	10.50	3.70	3.90	3.80	0.45	17.96		
30.5	45		Cum	1	14.50	3.00	4.40	3.70	0.45	24.14		
45	50		Cum	1	5.00	4.40	4.80	4.60	0.45	10.35		
50	62.1		Cum	1	12.10	3.80	3.85	3.83	0.45	20.83		
62.1	67.1		Cum	1	5.00	5.00	4.95	4.98	0.45	11.19		
67.1	80		Cum	1	12.90	4.70	6.15	5.43	0.45	31.49		
80	95		Cum	1	15.00	6.15	6.10	6.13	0.45	41.34		
95	110		Cum	1	15.00	6.10	5.35	5.73	0.45	38.64		
110	125		Cum	1	15.00	5.35	4.80	5.08	0.45	34.26		
125	140		Cum	1	15.00	4.80	4.70	4.75	0.45	32.06		
140	141.2		Cum	1	1.20	4.70	4.70	4.70	0.45	2.54		
		Railway Under Bridge										
0	26		Cum	1	26.00	4.90	4.90	4.90	0.30	38.22		
		Bharath Store (W1411)										
		North to South										
0	15		Cum	1	15.00	5.15	5.35	5.25	0.45	35.44		
15	30		Cum	1	15.00	3.80	5.10	4.45	0.45	30.04		
30	45		Cum	1	15.00	5.10	5.30	5.20	0.45	35.10		
45	60		Cum	1	15.00	5.30	5.10	5.20	0.45	35.10		
60	75		Cum	1	15.00	5.10	5.40	5.25	0.45	35.44		
75	88.4		Cum	1	13.40	5.40	5.55	5.48	0.45	33.01		
									Total Executed Quantity	**3018.14**	**60.00**	**181089.00**
									Tender Quantity	**3038.15**		

Scanned by CamScanner

Item no.10		Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications and as per the directions of the Engineer-in-charge of the work											
		Sadique Layout											
		Fathima Furniture Oppo. Road											
		South to North											
0	9.8		Sqm	1	9.80	4.95	4.70	4.83		47.29			
9.8	15		Sqm	1	5.20	5.60	5.35	5.48		28.47			
15	30		Sqm	1	15.00	5.35	5.45	5.40		81.00			
30	38.9		Sqm	1	8.90	5.45	5.50	5.48		48.73			
		Cross Road 1 (W1062)											
		East to West											
0	15		Sqm	1	15.00	6.40	6.45	6.43		96.38			
15	29.5		Sqm	1	14.50	6.45	6.30	6.38		92.44			
		Cross Road 2 (W1060)											
		East to West											
0	15		Sqm	1	15.00	6.10	6.30	6.20		93.00			
15	30		Sqm	1	15.00	6.30	5.70	6.00		90.00			
30	37.8		Sqm	1	7.80	5.70	5.60	5.65		44.07			
		3rd Cross Road (W1543)											
		North to South											
0	15		Sqm	1	15.00	6.25	5.80	6.03		90.38			
15	30		Sqm	1	15.00	5.80	6.00	5.90		88.50			
30	35		Sqm	1	5.00	6.00	6.00	6.00		30.00			
35	38.8		Sqm	1	3.80	6.80	6.80	6.80		25.84			
0	5.3		Sqm	1	5.30	5.30	5.40	5.35		28.36			
5.3	15		Sqm	1	9.70	4.40	5.30	4.85		47.05			
15	30		Sqm	1	15.00	5.30	5.75	5.53		82.88			
30	45		Sqm	1	15.00	5.75	5.30	5.53		82.88			
45	60		Sqm	1	15.00	5.30	4.70	5.00		75.00			
60	75		Sqm	1	15.00	4.70	4.40	4.55		68.25			
75	76.1		Sqm	1	1.10	4.40	4.40	4.40		4.84			
		4th Cross Road (W1555)											
		South to North											
0	15		Sqm	1	15.00	4.30	4.45	4.38		65.63			
15	30		Sqm	1	15.00	4.45	4.50	4.48		67.13			
30	33.8		Sqm	1	3.80	4.50	4.35	4.43		16.82			
33.8	37.2		Sqm	1	3.40	5.00	5.00	5.00		17.00			
37.2	45		Sqm	1	7.80	4.20	4.65	4.43		34.52			
45	60		Sqm	1	15.00	4.65	4.65	4.65		69.75			
60	65.2		Sqm	1	5.20	4.65	4.50	4.58		23.79			
65.2	74.5		Sqm	1	9.30	3.75	4.05	3.90		36.27			
		5th Cross Road (W1559)											
		South to North											
0	12.5		Sqm	1	12.50	3.40	3.90	3.65		45.63			
12.5	19.8		Sqm	1	7.30	4.80	4.50	4.65		33.95			
19.8	26.5		Sqm	1	6.70	5.20	5.40	5.30		35.51			
26.5	35		Sqm	1	8.50	4.75	4.35	4.55		38.68			
35	50		Sqm	1	15.00	4.35	3.50	3.93		58.88			
50	65		Sqm	1	15.00	3.50	3.50	3.50		52.50			
65	75.5		Sqm	1	10.50	3.50	2.55	3.03		31.76			
		5th A Cross Road (W1559)											
		North to South											
0	10.5		Sqm	1	10.50	5.20	6.00	5.60		58.80			
10.5	20		Sqm	1	9.50	2.80	2.70	2.75		26.13			
		Royal Fabricators Road (W171)											
		North to South											
0	15		Sqm	1	15.00	5.50	5.95	5.73		85.88			
15	30		Sqm	1	15.00	5.95	6.00	5.98		89.63			
30	41.3		Sqm	1	11.30	6.00	4.90	5.45		61.59			
		Star Clinic Beside Road (W1513)											
		North to South											
0	15		Sqm	1	15.00	5.00	4.80	4.90		73.50			
15	30		Sqm	1	15.00	4.80	5.00	4.90		73.50			
30	41		Sqm	1	11.00	5.00	4.15	4.58		50.33			

Scanned by CamScanner

		Al Hadi Chicken Centre Oppo. Road (W1521)										
		South to North										
0	15		Sqm	1	15.00	4.45	4.90	4.68		70.13		
15	30		Sqm	1	15.00	4.90	5.05	4.98		74.63		
30	43		Sqm	1	13.00	5.05	5.40	5.23		67.93		
		Bharath Nagara										
		N R Bike Point Beside (W0782)										
		East to West										
0	15		Sqm	1	15.00	5.15	5.30	5.23		78.38		
15	30		Sqm	1	15.00	5.30	5.20	5.25		78.75		
30	45		Sqm	1	15.00	5.20	5.30	5.25		78.75		
45	60		Sqm	1	15.00	5.30	5.30	5.30		79.50		
60	75		Sqm	1	15.00	5.30	5.40	5.35		80.25		
75	90		Sqm	1	15.00	5.40	5.30	5.35		80.25		
90	105		Sqm	1	15.00	5.30	5.30	5.30		79.50		
105	120		Sqm	1	15.00	5.30	5.10	5.20		78.00		
120	121		Sqm	1	1.00	5.10	5.10	5.10		5.10		
121	127		Sqm	1	6.00	6.10	6.10	6.10		36.60		
		Cross Road 1 (W1185)										
		North to South										
0	15		Sqm	1	15.00	5.30	5.30	5.30		79.50		
15	20.5		Sqm	1	5.50	5.30	5.30	5.30		29.15		
20.5	24.5		Sqm	1	4.00	2.50	2.50	2.50		10.00		
		Cross Road 2 (W1193)										
		North to South										
0	15		Sqm	1	15.00	5.35	5.40	5.38		80.63		
15	28		Sqm	1	13.00	5.40	4.80	5.10		66.30		
		Cross Road 3 (W1197)										
		North to South										
0	15		Sqm	1	15.00	4.50	5.15	4.83		72.38		
15	18.6		Sqm	1	3.60	5.15	5.15	5.15		18.54		
18.6	23.5		Sqm	1	4.90	3.40	3.40	3.40		16.66		
23.5	27		Sqm	1	3.50	5.15	5.10	5.13		17.94		
		Cross Road 4 (W1201)										
		North to South										
0	8.8		Sqm	1	8.80	5.95	6.00	5.98		52.58		
8.8	15		Sqm	1	6.20	4.30	5.10	4.70		29.14		
15	27.3		Sqm	1	12.30	5.10	4.90	5.00		61.50		
		Cross Road 5 (W1183)										
		North to South										
0	15		Sqm	1	15.00	5.10	5.00	5.05		75.75		
15	30		Sqm	1	15.00	5.00	5.00	5.00		75.00		
30	34		Sqm	1	4.00	5.00	4.90	4.95		19.80		
		R A Store Oppo. Road (W0966)										
		East to West										
0	15		Sqm	1	15.00	3.60	3.80	3.70		55.50		
15	24.5		Sqm	1	9.50	3.80	3.90	3.85		36.58		
		Sameer Salon Road (W1425)										
		South to North										
0	4.2		Sqm	1	4.20	3.60	3.60	3.60		15.12		
4.2	15		Sqm	1	10.80	2.60	3.30	2.95		31.86		
15	30		Sqm	1	15.00	3.30	3.60	3.45		51.75		
30	45		Sqm	1	15.00	3.60	3.70	3.65		54.75		
45	60		Sqm	1	15.00	3.70	3.80	3.75		56.25		
60	62.2		Sqm	1	2.20	3.80	3.80	3.80		8.36		
62.2	63.4		Sqm	1	0.00	3.80	5.30	4.55		0.00		
63.4	67		Sqm	1	3.60	3.80	3.80	3.80		13.68		
67	80		Sqm	1	13.00	3.80	4.00	3.90		50.70		
80	95		Sqm	1	15.00	4.00	3.90	3.95		59.25		
95	110		Sqm	1	15.00	3.90	3.70	3.80		57.00		
110	125		Sqm	1	15.00	3.70	3.90	3.80		57.00		
125	129		Sqm	1	4.00	3.90	3.90	3.90		15.60		
		M S Pharma Oppo. Road (W1441)										
		North to South										
0	15		Sqm	1	15.00	3.80	3.40	3.60		54.00		

Scanned by CamScanner

15	30		Sqm	1	15.00	3.40	3.80	3.60		54.00		
30	45		Sqm	1	15.00	3.80	3.80	3.80		57.00		
45	53.1		Sqm	1	8.10	3.80	3.80	3.80		30.78		
		Cross Road 1 (W0982)										
		East to West										
0	15		Sqm	1	15.00	3.70	3.60	3.65		54.75		
15	30		Sqm	1	15.00	3.60	3.60	3.60		54.00		
30	42.9		Sqm	1	12.90	3.60	3.80	3.70		47.73		
		Cross Road 2 (W0978)										
		East to West										
0	15		Sqm	1	15.00	3.40	3.40	3.40		51.00		
15	23.1		Sqm	1	8.10	3.40	3.40	3.40		27.54		
23.1	28.7		Sqm	1	5.60	1.90	1.90	1.90		10.64		
		Inspire Public School Oppo. Road (W0990)										
		West to East										
0	15		Sqm	1	15.00	3.90	4.60	4.25		63.75		
15	20		Sqm	1	5.00	4.60	4.85	4.73		23.63		
		Cross Road 4 (W0984)										
		East to West										
0	15		Sqm	1	15.00	4.80	4.90	4.85		72.75		
15	19.5		Sqm	1	4.50	4.90	5.00	4.95		22.28		
		Cross Road 3 (W0984)										
		West to East										
0	15		Sqm	1	15.00	4.35	4.20	4.28		64.13		
15	24.9		Sqm	1	9.90	4.20	4.20	4.20		41.58		
		Cross Road 2 (W0980)										
		East to West										
0	13.9		Sqm	1	13.90	4.50	4.50	4.50		62.55		
13.9	18.6		Sqm	1	4.70	4.00	4.00	4.00		18.80		
18.6	20.3		Sqm	1	1.70	2.60	2.60	2.60		4.42		
20.3	25.4		Sqm	1	5.10	3.30	3.30	3.30		16.83		
		Cross Road 1 (W0980)										
		West to East										
0	15		Sqm	1	15.00	4.90	4.90	4.90		73.50		
15	24.1		Sqm	1	9.10	4.90	4.90	4.90		44.59		
		Masjid-E-Uqba Road (W1483)										
		North to South										
0	8		Sqm	1	8.00	5.00	4.30	4.65		37.20		
8	20		Sqm	1	12.00	3.65	3.70	3.68		44.10		
20	30.5		Sqm	1	10.50	3.70	3.90	3.80		39.90		
30.5	45		Sqm	1	14.50	3.00	4.40	3.70		53.65		
45	50		Sqm	1	5.00	4.40	4.80	4.60		23.00		
50	62.1		Sqm	1	12.10	3.80	3.85	3.83		46.28		
62.1	67.1		Sqm	1	5.00	5.00	4.95	4.98		24.88		
67.1	80		Sqm	1	12.90	4.70	6.15	5.43		69.98		
80	95		Sqm	1	15.00	6.15	6.10	6.13		91.88		
95	110		Sqm	1	15.00	6.10	5.35	5.73		85.88		
110	125		Sqm	1	15.00	5.35	4.80	5.08		76.13		
125	140		Sqm	1	15.00	4.80	4.70	4.75		71.25		
140	141.2		Sqm	1	1.20	4.70	4.70	4.70		5.64		
		Bharath Store (W1411)										
		North to South										
0	15		Sqm	1	15.00	5.15	5.35	5.25		78.75		
15	30		Sqm	1	15.00	3.80	5.10	4.45		66.75		
30	45		Sqm	1	15.00	5.10	5.30	5.20		78.00		
45	60		Sqm	1	15.00	5.30	5.10	5.20		78.00		
60	75		Sqm	1	15.00	5.10	5.40	5.25		78.75		
75	88.4		Sqm	1	13.40	5.40	5.55	5.48		73.37		
									Total Executed Quantity	**6622.05**	**7.00**	**46355.00**
									Tender Quantity	**6751.45**		
Item no.11		Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Sadique Layout										

Scanned by CamScanner

		Fathima Furniture Oppo Road										
		South to North										
0	9.8		Cum	1	9.80	4.95	4.70	4.83	0.15	7.09		
9.8	15		Cum	1	5.20	5.60	5.35	5.48	0.15	4.27		
15	30		Cum	1	15.00	5.35	5.45	5.40	0.15	12.15		
30	38.9		Cum	1	8.90	5.45	5.50	5.48	0.15	7.31		
0	0											
0	0	Cross Road 1 (W1062)										
0	0	East to West										
0	15		Cum	1	15.00	6.40	6.45	6.43	0.15	14.46		
15	29.5		Cum	1	14.50	6.45	6.30	6.38	0.15	13.87		
		Cross Road 2 (W1060)										
		East to West										
0	15		Cum	1	15.00	6.10	6.30	6.20	0.15	13.95		
15	30		Cum	1	15.00	6.30	5.70	6.00	0.15	13.50		
30	37.8		Cum	1	7.80	5.70	5.60	5.65	0.15	6.61		
		3rd Cross Road (W1543)										
		North to South										
0	15		Cum	1	15.00	6.25	5.80	6.03	0.15	13.56		
15	30		Cum	1	15.00	5.80	6.00	5.90	0.15	13.28		
30	35		Cum	1	5.00	6.00	6.00	6.00	0.15	4.50		
35	38.8		Cum	1	3.80	6.80	6.80	6.80	0.15	3.88		
0	5.3		Cum	1	5.30	5.30	5.40	5.35	0.15	4.25		
5.3	15		Cum	1	9.70	4.40	5.30	4.85	0.15	7.06		
15	30		Cum	1	15.00	5.30	5.75	5.53	0.15	12.43		
30	45		Cum	1	15.00	5.75	5.30	5.53	0.15	12.43		
45	60		Cum	1	15.00	5.30	4.70	5.00	0.15	11.25		
60	75		Cum	1	15.00	4.70	4.40	4.55	0.15	10.24		
75	76.1		Cum	1	1.10	4.40	4.40	4.40	0.15	0.73		
		4th Cross Road (W1555)										
		South to North										
0	15		Cum	1	15.00	4.30	4.45	4.38	0.15	9.84		
15	30		Cum	1	15.00	4.45	4.50	4.48	0.15	10.07		
30	33.8		Cum	1	3.80	4.50	4.35	4.43	0.15	2.52		
33.8	37.2		Cum	1	3.40	5.00	5.00	5.00	0.15	2.55		
37.2	45		Cum	1	7.80	4.20	4.65	4.43	0.15	5.18		
45	60		Cum	1	15.00	4.65	4.65	4.65	0.15	10.46		
60	65.2		Cum	1	5.20	4.65	4.50	4.58	0.15	3.57		
65.2	74.5		Cum	1	9.30	3.75	4.05	3.90	0.15	5.44		
		5th Cross Road (W1559)										
		South to North										
0	12.5		Cum	1	12.50	3.40	3.90	3.65	0.15	6.84		
12.5	19.8		Cum	1	7.30	4.80	4.50	4.65	0.15	5.09		
19.8	26.5		Cum	1	6.70	5.20	5.40	5.30	0.15	5.33		
26.5	35		Cum	1	8.50	4.75	4.35	4.55	0.15	5.80		
35	50		Cum	1	15.00	4.35	3.50	3.93	0.15	8.83		
50	65		Cum	1	15.00	3.50	3.50	3.50	0.15	7.88		
65	75.5		Cum	1	10.50	3.50	2.55	3.03	0.15	4.76		
		5th A Cross Road (W1559)										
		North to South										
0	10.5		Cum	1	10.50	5.20	6.00	5.60	0.15	8.82		
10.5	20		Cum	1	9.50	2.80	2.70	2.75	0.15	3.92		
		Royal Fabricators Road (W171)										
		North to South										
0	15		Cum	1	15.00	5.50	5.95	5.73	0.15	12.88		
15	30		Cum	1	15.00	5.95	6.00	5.98	0.15	13.44		
30	41.3		Cum	1	11.30	6.00	4.90	5.45	0.15	9.24		
		Star Clinic Beside Road (W1513)										
		North to South										
0	15		Cum	1	15.00	5.00	4.80	4.90	0.15	11.03		
15	30		Cum	1	15.00	4.80	5.00	4.90	0.15	11.03		
30	41		Cum	1	11.00	5.00	4.15	4.58	0.15	7.55		
		Al Hadi Chicken Centre Oppo Road (W1521)										
		South to North										
0	15		Cum	1	15.00	4.45	4.90	4.68	0.15	10.52		

Scanned by CamScanner

15	30		Cum	1	15.00	4.90	5.05	4.98	0.15	11.19		
30	43		Cum	1	13.00	5.05	5.40	5.23	0.15	10.19		
		Bharath Nagara										
		N R Bike Point Beside (W0782)										
		Last to West										
0	15		Cum	1	15.00	5.15	5.30	5.23	0.15	11.76		
15	30		Cum	1	15.00	5.30	5.20	5.25	0.15	11.81		
30	45		Cum	1	15.00	5.20	5.30	5.25	0.15	11.81		
45	60		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
60	75		Cum	1	15.00	5.30	5.40	5.35	0.15	12.04		
75	90		Cum	1	15.00	5.40	5.30	5.35	0.15	12.04		
90	105		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
105	120		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
120	121		Cum	1	1.00	5.10	5.10	5.10	0.15	0.77		
121	127		Cum	1	6.00	6.10	6.10	6.10	0.15	5.49		
		Cross Road 1 (W1185)										
		North to South										
0	15		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
15	20.5		Cum	1	5.50	5.30	5.30	5.30	0.15	4.37		
20.5	24.5		Cum	1	4.00	2.50	2.50	2.50	0.15	1.50		
		Cross Road 2 (W1193)										
		North to South										
0	15		Cum	1	15.00	5.35	5.40	5.38	0.15	12.09		
15	28		Cum	1	13.00	5.40	4.80	5.10	0.15	9.95		
		Cross Road 3 (W1197)										
		North to South										
0	15		Cum	1	15.00	4.50	5.15	4.83	0.15	10.86		
15	18.6		Cum	1	3.60	5.15	5.15	5.15	0.15	2.78		
18.6	23.5		Cum	1	4.90	3.40	3.40	3.40	0.15	2.50		
23.5	27		Cum	1	3.50	5.15	5.10	5.13	0.15	2.69		
		Cross Road 4 (W1201)										
		North to South										
0	8.8		Cum	1	8.80	5.95	6.00	5.98	0.15	7.89		
8.8	15		Cum	1	6.20	4.30	5.10	4.70	0.15	4.37		
15	27.3		Cum	1	12.30	5.10	4.90	5.00	0.15	9.23		
		Cross Road 5 (W1183)										
		North to South										
0	15		Cum	1	15.00	5.10	5.00	5.05	0.15	11.36		
15	30		Cum	1	15.00	5.00	5.00	5.00	0.15	11.25		
30	34		Cum	1	4.00	5.00	4.90	4.95	0.15	2.97		
		R A Store Oppo. Road (W0966)										
		East to West										
0	15		Cum	1	15.00	3.60	3.80	3.70	0.15	8.33		
15	24.5		Cum	1	9.50	3.80	3.90	3.85	0.15	5.49		
		Sameer Salon Road (W1425)										
		South to North										
0	4.2		Cum	1	4.20	3.60	3.60	3.60	0.15	2.27		
4.2	15		Cum	1	10.80	2.60	3.30	2.95	0.15	4.78		
15	30		Cum	1	15.00	3.30	3.60	3.45	0.15	7.76		
30	45		Cum	1	15.00	3.60	3.70	3.65	0.15	8.21		
45	60		Cum	1	15.00	3.70	3.80	3.75	0.15	8.44		
60	62.2		Cum	1	2.20	3.80	3.80	3.80	0.15	1.25		
62.2	63.4	Culvert	Cum	1	0.00	3.80	5.30	4.55	0.15	0.00		
63.4	67		Cum	1	3.60	3.80	3.80	3.80	0.15	2.05		
67	80		Cum	1	13.00	3.80	4.00	3.90	0.15	7.61		
80	95		Cum	1	15.00	4.00	3.90	3.95	0.15	8.89		
95	110		Cum	1	15.00	3.90	3.70	3.80	0.15	8.55		
110	125		Cum	1	15.00	3.70	3.90	3.80	0.15	8.55		
125	129		Cum	1	4.00	3.90	3.90	3.90	0.15	2.34		
		M S Pharma Oppo Road (W1441)										
		North to South										
0	15		Cum	1	15.00	3.80	3.40	3.60	0.15	8.10		
15	30		Cum	1	15.00	3.40	3.80	3.60	0.15	8.10		
30	45		Cum	1	15.00	3.80	3.80	3.80	0.15	8.55		
45	53.1		Cum	1	8.10	3.80	3.80	3.80	0.15	4.62		

Scanned by CamScanner

		Cross Road 1 (W0982)										
		East to West										
0	15		Cum	1	15.00	3.70	3.60	3.65	0.15	8.21		
15	30		Cum	1	15.00	3.60	3.60	3.60	0.15	8.10		
30	42.9		Cum	1	12.90	3.60	3.80	3.70	0.15	7.16		
		Cross Road 2 (W0978)										
		East to West										
0	15		Cum	1	15.00	3.40	3.40	3.40	0.15	7.65		
15	23.1		Cum	1	8.10	3.40	3.40	3.40	0.15	4.13		
23.1	28.7		Cum	1	5.60	1.90	1.90	1.90	0.15	1.60		
		Inspire Public School Oppo. Road (W0990)										
		West to East										
0	15		Cum	1	15.00	3.90	4.60	4.25	0.15	9.56		
15	20		Cum	1	5.00	4.60	4.85	4.73	0.15	3.54		
		Cross Road 4 (W0984)										
		East to West										
0	15		Cum	1	15.00	4.80	4.90	4.85	0.15	10.91		
15	19.5		Cum	1	4.50	4.90	5.00	4.95	0.15	3.34		
		Cross Road 3 (W0984)										
		West to East										
0	15		Cum	1	15.00	4.35	4.20	4.28	0.15	9.62		
15	24.9		Cum	1	9.90	4.20	4.20	4.20	0.15	6.24		
		Cross Road 2 (W0980)										
		East to West										
0	13.9		Cum	1	13.90	4.50	4.50	4.50	0.15	9.38		
13.9	18.6		Cum	1	4.70	4.00	4.00	4.00	0.15	2.82		
18.6	20.3		Cum	1	1.70	2.60	2.60	2.60	0.15	0.66		
20.3	25.4		Cum	1	5.10	3.30	3.30	3.30	0.15	2.52		
		Cross Road 1 (W0980)										
		West to East										
0	15		Cum	1	15.00	4.90	4.90	4.90	0.15	11.03		
15	24.1		Cum	1	9.10	4.90	4.90	4.90	0.15	6.69		
		Masjid-E-Uqba Road (W1483)										
		North to South										
0	8		Cum	1	8.00	5.00	4.30	4.65	0.15	5.58		
8	20		Cum	1	12.00	3.65	3.70	3.68	0.15	6.62		
20	30.5		Cum	1	10.50	3.70	3.90	3.80	0.15	5.99		
30.5	45		Cum	1	14.50	3.00	4.40	3.70	0.15	8.05		
45	50		Cum	1	5.00	4.40	4.80	4.60	0.15	3.45		
50	62.1		Cum	1	12.10	3.80	3.85	3.83	0.15	6.94		
62.1	67.1		Cum	1	5.00	5.00	4.95	4.98	0.15	3.73		
67.1	80		Cum	1	12.90	4.70	6.15	5.43	0.15	10.50		
80	95		Cum	1	15.00	6.15	6.10	6.13	0.15	13.78		
95	110		Cum	1	15.00	6.10	5.35	5.73	0.15	12.88		
110	125		Cum	1	15.00	5.35	4.80	5.08	0.15	11.42		
125	140		Cum	1	15.00	4.80	4.70	4.75	0.15	10.69		
140	141.2		Cum	1	1.20	4.70	4.70	4.70	0.15	0.85		
		Bharath Store (W1411)										
		North to South										
0	15		Cum	1	15.00	5.15	5.35	5.25	0.15	11.81		
15	30		Cum	1	15.00	3.80	5.10	4.45	0.15	10.01		
30	45		Cum	1	15.00	5.10	5.30	5.20	0.15	11.70		
45	60		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
60	75		Cum	1	15.00	5.10	5.40	5.25	0.15	11.81		
75	88.4		Cum	1	13.40	5.40	5.55	5.48	0.15	11.00		
									Total Executed Quantity	**993.31**	**2200.00**	**2185275.00**
									Tender Quantity	**1012.72**		
Item no.12		Providing and Constructing dry lean cement concrete mix CC1:5:10 Base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum over a prepared sub-base coarse and fine aggregate conforming to IS: 383-2016, aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Sadique Layout										
		Fathima Furniture Oppo Road										
		South to North										

Scanned by CamScanner

0	9.8		Cum	1	9.80	4.95	4.70	4.83	0.15	7.09		
9.8	15		Cum	1	5.20	5.60	5.35	5.48	0.15	4.27		
15	30		Cum	1	15.00	5.35	5.45	5.40	0.15	12.15		
30	38.9		Cum	1	8.90	5.45	5.50	5.48	0.15	7.31		
		Cross Road 1 (W1062)										
		East to West										
0	15		Cum	1	15.00	6.40	6.45	6.43	0.15	14.46		
15	29.5		Cum	1	14.50	6.45	6.30	6.38	0.15	13.87		
		Cross Road 2 (W1060)										
		East to West										
0	15		Cum	1	15.00	6.10	6.30	6.20	0.15	13.95		
15	30		Cum	1	15.00	6.30	5.70	6.00	0.15	13.50		
30	37.8		Cum	1	7.80	5.70	5.60	5.65	0.15	6.61		
		3rd Cross Road (W1543)										
		North to South										
0	15		Cum	1	15.00	6.25	5.80	6.03	0.15	13.56		
15	30		Cum	1	15.00	5.80	6.00	5.90	0.15	13.28		
30	35		Cum	1	5.00	6.00	6.00	6.00	0.15	4.50		
35	38.8		Cum	1	3.80	6.80	6.80	6.80	0.15	3.88		
0	5.3		Cum	1	5.30	5.30	5.40	5.35	0.15	4.25		
5.3	15		Cum	1	9.70	4.40	5.30	4.85	0.15	7.06		
15	30		Cum	1	15.00	5.30	5.75	5.53	0.15	12.43		
30	45		Cum	1	15.00	5.75	5.30	5.53	0.15	12.43		
45	60		Cum	1	15.00	5.30	4.70	5.00	0.15	11.25		
60	75		Cum	1	15.00	4.70	4.40	4.55	0.15	10.24		
75	76.1		Cum	1	1.10	4.40	4.40	4.40	0.15	0.73		
		4th Cross Road (W1555)										
		South to North										
0	15		Cum	1	15.00	4.30	4.45	4.38	0.15	9.84		
15	30		Cum	1	15.00	4.45	4.50	4.48	0.15	10.07		
30	33.8		Cum	1	3.80	4.50	4.35	4.43	0.15	2.52		
33.8	37.2		Cum	1	3.40	5.00	5.00	5.00	0.15	2.55		
37.2	45		Cum	1	7.80	4.20	4.65	4.43	0.15	5.18		
45	60		Cum	1	15.00	4.65	4.65	4.65	0.15	10.46		
60	65.2		Cum	1	5.20	4.65	4.50	4.58	0.15	3.57		
65.2	74.5		Cum	1	9.30	3.75	4.05	3.90	0.15	5.44		
		5th Cross Road (W1559)										
		South to North										
0	12.5		Cum	1	12.50	3.40	3.90	3.65	0.15	6.84		
12.5	19.8		Cum	1	7.30	4.80	4.50	4.65	0.15	5.09		
19.8	26.5		Cum	1	6.70	5.20	5.40	5.30	0.15	5.33		
26.5	35		Cum	1	8.50	4.75	4.35	4.55	0.15	5.80		
35	50		Cum	1	15.00	4.35	3.50	3.93	0.15	8.83		
50	65		Cum	1	15.00	3.50	3.50	3.50	0.15	7.88		
65	75.5		Cum	1	10.50	3.50	2.55	3.03	0.15	4.76		
		5th A Cross Road (W1559)										
		North to South										
0	10.5		Cum	1	10.50	5.20	6.00	5.60	0.15	8.82		
10.5	20		Cum	1	9.50	2.80	2.70	2.75	0.15	3.92		
		Royal Fabricators Road (W171)										
		North to South										
0	15		Cum	1	15.00	5.50	5.95	5.73	0.15	12.88		
15	30		Cum	1	15.00	5.95	6.00	5.98	0.15	13.44		
30	41.3		Cum	1	11.30	6.00	4.90	5.45	0.15	9.24		
		Star Clinic Beside Road (W1513)										
		North to South										
0	15		Cum	1	15.00	5.00	4.80	4.90	0.15	11.03		
15	30		Cum	1	15.00	4.80	5.00	4.90	0.15	11.03		
30	41		Cum	1	11.00	5.00	4.15	4.58	0.15	7.55		
		Al Hadi Chicken Centre Oppo Road (W1521)										
		South to North										
0	15		Cum	1	15.00	4.45	4.90	4.68	0.15	10.52		
15	30		Cum	1	15.00	4.90	5.05	4.98	0.15	11.19		
30	43		Cum	1	13.00	5.05	5.40	5.23	0.15	10.19		

Scanned by CamScanner

		Bharath Nagara										
		N R Bike Point Beside (W0782)										
		East to West										
0	15		Cum	1	15.00	5.15	5.30	5.23	0.15	11.76		
15	30		Cum	1	15.00	5.30	5.20	5.25	0.15	11.81		
30	45		Cum	1	15.00	5.20	5.30	5.25	0.15	11.81		
45	60		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
60	75		Cum	1	15.00	5.30	5.40	5.35	0.15	12.04		
75	90		Cum	1	15.00	5.40	5.30	5.35	0.15	12.04		
90	105		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
105	120		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
120	121		Cum	1	1.00	5.10	5.10	5.10	0.15	0.77		
121	127		Cum	1	6.00	6.10	6.10	6.10	0.15	5.49		
		Cross Road 1 (W1185)										
		North to South										
0	15		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
15	20.5		Cum	1	5.50	5.30	5.30	5.30	0.15	4.37		
20.5	24.5		Cum	1	4.00	2.50	2.50	2.50	0.15	1.50		
		Cross Road 2 (W1193)										
		North to South										
0	15		Cum	1	15.00	5.35	5.40	5.38	0.15	12.09		
15	28		Cum	1	13.00	5.40	4.80	5.10	0.15	9.95		
		Cross Road 3 (W1197)										
		North to South										
0	15		Cum	1	15.00	4.50	5.15	4.83	0.15	10.86		
15	18.6		Cum	1	3.60	5.15	5.15	5.15	0.15	2.78		
18.6	23.5		Cum	1	4.90	3.40	3.40	3.40	0.15	2.50		
23.5	27		Cum	1	3.50	5.15	5.10	5.13	0.15	2.69		
		Cross Road 4 (W1201)										
		North to South										
0	8.8		Cum	1	8.80	5.95	6.00	5.98	0.15	7.89		
8.8	15		Cum	1	6.20	4.30	5.10	4.70	0.15	4.37		
15	27.3		Cum	1	12.30	5.10	4.90	5.00	0.15	9.23		
		Cross Road 5 (W1183)										
		North to South										
0	15		Cum	1	15.00	5.10	5.00	5.05	0.15	11.36		
15	30		Cum	1	15.00	5.00	5.00	5.00	0.15	11.25		
30	34		Cum	1	4.00	5.00	4.90	4.95	0.15	2.97		
		R A Store Oppo Road (W0966)										
		East to West										
0	15		Cum	1	15.00	3.60	3.80	3.70	0.15	8.33		
15	24.5		Cum	1	9.50	3.80	3.90	3.85	0.15	5.49		
		Sameer Salon Road (W1425)										
		South to North										
0	4.2		Cum	1	4.20	3.60	3.60	3.60	0.15	2.27		
4.2	15		Cum	1	10.80	2.60	3.30	2.95	0.15	4.78		
15	30		Cum	1	15.00	3.30	3.60	3.45	0.15	7.76		
30	45		Cum	1	15.00	3.60	3.70	3.65	0.15	8.21		
45	60		Cum	1	15.00	3.70	3.80	3.75	0.15	8.44		
60	62.2		Cum	1	2.20	3.80	3.80	3.80	0.15	1.25		
62.2	63.4	Culvert	Cum	1	0.00	3.80	5.30	4.55	0.15	0.00		
63.4	67		Cum	1	3.60	3.80	3.80	3.80	0.15	2.05		
67	80		Cum	1	13.00	3.80	4.00	3.90	0.15	7.61		
80	95		Cum	1	15.00	4.00	3.90	3.95	0.15	8.89		
95	110		Cum	1	15.00	3.90	3.70	3.80	0.15	8.55		
110	125		Cum	1	15.00	3.70	3.90	3.80	0.15	8.55		
125	129		Cum	1	4.00	3.90	3.90	3.90	0.15	2.34		
		M S Pharma Oppo Road (W1441)										
		North to South										
0	15		Cum	1	15.00	3.80	3.40	3.60	0.15	8.10		
15	30		Cum	1	15.00	3.40	3.80	3.60	0.15	8.10		
30	45		Cum	1	15.00	3.80	3.80	3.80	0.15	8.55		
45	53.1		Cum	1	8.10	3.80	3.80	3.80	0.15	4.62		
		Cross Road 1 (W0982)										
		East to West										

Scanned by CamScanner

0	15		Cum	1	15.00	3.70	3.60	3.65	0.15	8.21		
15	30		Cum	1	15.00	3.60	3.60	3.60	0.15	8.10		
30	42.9		Cum	1	12.90	3.60	3.80	3.70	0.15	7.16		
		Cross Road 2 (W0978)										
		East to West										
0	15		Cum	1	15.00	3.40	3.40	3.40	0.15	7.65		
15	23.1		Cum	1	8.10	3.40	3.40	3.40	0.15	4.13		
23.1	28.7		Cum	1	5.60	1.90	1.90	1.90	0.15	1.60		
		Inspire Public School Oppo. Road (W0990)										
		West to East										
0	15		Cum	1	15.00	3.90	4.60	4.25	0.15	9.56		
15	20		Cum	1	5.00	4.60	4.85	4.73	0.15	3.54		
		Cross Road 4 (W0984)										
		East to West										
0	15		Cum	1	15.00	4.80	4.90	4.85	0.15	10.91		
15	19.5		Cum	1	4.50	4.90	5.00	4.95	0.15	3.34		
		Cross Road 3 (W0984)										
		West to East										
0	15		Cum	1	15.00	4.35	4.20	4.28	0.15	9.62		
15	24.9		Cum	1	9.90	4.20	4.20	4.20	0.15	6.24		
		Cross Road 2 (W0980)										
		East to West										
0	13.9		Cum	1	13.90	4.50	4.50	4.50	0.15	9.38		
13.9	18.6		Cum	1	4.70	4.00	4.00	4.00	0.15	2.82		
18.6	20.3		Cum	1	1.70	2.60	2.60	2.60	0.15	0.66		
20.3	25.4		Cum	1	5.10	3.30	3.30	3.30	0.15	2.52		
		Cross Road 1 (W0980)										
		West to East										
0	15		Cum	1	15.00	4.90	4.90	4.90	0.15	11.03		
15	24.1		Cum	1	9.10	4.90	4.90	4.90	0.15	6.69		
		Masjid-E-Uqba Road (W1483)										
		North to South										
0	8		Cum	1	8.00	5.00	4.30	4.65	0.15	5.58		
8	20		Cum	1	12.00	3.65	3.70	3.68	0.15	6.62		
20	30.5		Cum	1	10.50	3.70	3.90	3.80	0.15	5.99		
30.5	45		Cum	1	14.50	3.00	4.40	3.70	0.15	8.05		
45	50		Cum	1	5.00	4.40	4.80	4.60	0.15	3.45		
50	62.1		Cum	1	12.10	3.80	3.85	3.83	0.15	6.94		
62.1	67.1		Cum	1	5.00	5.00	4.95	4.98	0.15	3.73		
67.1	80		Cum	1	12.90	4.70	6.15	5.43	0.15	10.50		
80	95		Cum	1	15.00	6.15	6.10	6.13	0.15	13.78		
95	110		Cum	1	15.00	6.10	5.35	5.73	0.15	12.88		
110	125		Cum	1	15.00	5.35	4.80	5.08	0.15	11.42		
125	140		Cum	1	15.00	4.80	4.70	4.75	0.15	10.69		
140	141.2		Cum	1	1.20	4.70	4.70	4.70	0.15	0.85		
		Railway Under Bridge										
0	26		Cum	1	26.00	4.90	4.90	4.90	0.15	19.11		
		Bharath Store (W1411)										
		North to South										
0	15		Cum	1	15.00	5.15	5.35	5.25	0.15	11.81		
15	30		Cum	1	15.00	3.80	5.10	4.45	0.15	10.01		
30	45		Cum	1	15.00	5.10	5.30	5.20	0.15	11.70		
45	60		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
60	75		Cum	1	15.00	5.10	5.40	5.25	0.15	11.81		
75	88.4		Cum	1	13.40	5.40	5.55	5.48	0.15	11.00		
									Total Executed Quantity	**1012.42**	**4700.00**	**4758359.00**
									Tender Quantity	**1012.72**		

Scanned by CamScanner

Item no.13	Cement concrete pavement Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS 383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire chargedof machines,all lead and lift charges etc , complete as per specifications -and as per the directions of the Engineer-in-charge of the work

		Sadique Layout										
		Fathima Furniture Oppo. Road										
		South to North										
0	9.8		Cum	1	9.80	4.95	4.70	4.83	0.15	7.09		
9.8	15		Cum	1	5.20	5.60	5.35	5.48	0.15	4.27		
15	30		Cum	1	15.00	5.35	5.45	5.40	0.15	12.15		
30	38.9		Cum	1	8.90	5.45	5.50	5.48	0.15	7.31		
		Cross Road 1 (W1062)										
		East to West										
0	15		Cum	1	15.00	6.40	6.45	6.43	0.15	14.46		
15	29.5		Cum	1	14.50	6.45	6.30	6.38	0.15	13.87		
		Cross Road 2 (W1060)										
		East to West										
0	15		Cum	1	15.00	6.10	6.30	6.20	0.15	13.95		
15	30		Cum	1	15.00	6.30	5.70	6.00	0.15	13.50		
30	37.8		Cum	1	7.80	5.70	5.60	5.65	0.15	6.61		
		3rd Cross Road (W1543)										
		North to South										
0	15		Cum	1	15.00	6.25	5.80	6.03	0.15	13.56		
15	30		Cum	1	15.00	5.80	6.00	5.90	0.15	13.28		
30	35		Cum	1	5.00	6.00	6.00	6.00	0.15	4.50		
35	38.8		Cum	1	3.80	6.80	6.80	6.80	0.15	3.88		
0	5.3		Cum	1	5.30	5.30	5.40	5.35	0.15	4.25		
5.3	15		Cum	1	9.70	4.40	5.30	4.85	0.15	7.06		
15	30		Cum	1	15.00	5.30	5.75	5.53	0.15	12.43		
30	45		Cum	1	15.00	5.75	5.30	5.53	0.15	12.43		
45	60		Cum	1	15.00	5.30	4.70	5.00	0.15	11.25		
60	75		Cum	1	15.00	4.70	4.40	4.55	0.15	10.24		
75	76.1		Cum	1	1.10	4.40	4.40	4.40	0.15	0.73		
		4th Cross Road (W1555)										
		South to North										
0	15		Cum	1	15.00	4.30	4.45	4.38	0.15	9.84		
15	30		Cum	1	15.00	4.45	4.50	4.48	0.15	10.07		
30	33.8		Cum	1	3.80	4.50	4.35	4.43	0.15	2.52		
33.8	37.2		Cum	1	3.40	5.00	5.00	5.00	0.15	2.55		
37.2	45		Cum	1	7.80	4.20	4.65	4.43	0.15	5.18		
45	60		Cum	1	15.00	4.65	4.65	4.65	0.15	10.46		
60	65.2		Cum	1	5.20	4.65	4.50	4.58	0.15	3.57		
65.2	74.5		Cum	1	9.30	3.75	4.05	3.90	0.15	5.44		
		5th Cross Road (W1559)										
		South to North										
0	12.5		Cum	1	12.50	3.40	3.90	3.65	0.15	6.84		
12.5	19.8		Cum	1	7.30	4.80	4.50	4.65	0.15	5.09		
19.8	26.5		Cum	1	6.70	5.20	5.40	5.30	0.15	5.33		
26.5	35		Cum	1	8.50	4.75	4.35	4.55	0.15	5.80		
35	50		Cum	1	15.00	4.35	3.50	3.93	0.15	8.83		
50	65		Cum	1	15.00	3.50	3.50	3.50	0.15	7.88		
65	75.5		Cum	1	10.50	3.50	2.55	3.03	0.15	4.76		
		5th A Cross Road (W1559)										
		North to South										
0	10.5		Cum	1	10.50	5.20	6.00	5.60	0.15	8.82		
10.5	20		Cum	1	9.50	2.80	2.70	2.75	0.15	3.92		
		Royal Fabricators Road (W171)										
		North to South										
0	15		Cum	1	15.00	5.50	5.95	5.73	0.15	12.88		
15	30		Cum	1	15.00	5.95	6.00	5.98	0.15	13.44		
30	41.3		Cum	1	11.30	6.00	4.90	5.45	0.15	9.24		

Scanned by CamScanner

		Star Clinic Beside Road (W1513)										
		North to South										
0	15		Cum	1	15.00	5.00	4.80	4.90	0.15	11.03		
15	30		Cum	1	15.00	4.80	5.00	4.90	0.15	11.03		
30	41		Cum	1	11.00	5.00	4.15	4.58	0.15	7.55		
		Al Hadi Chicken Centre Oppo										
		South to North										
0	15		Cum	1	15.00	4.45	4.90	4.68	0.15	10.52		
15	30		Cum	1	15.00	4.90	5.05	4.98	0.15	11.19		
30	43		Cum	1	13.00	5.05	5.40	5.23	0.15	10.19		
		Bharath Nagara										
		N R Bike Point Beside (W0782)										
		East to West										
0	15		Cum	1	15.00	5.15	5.30	5.23	0.15	11.76		
15	30		Cum	1	15.00	5.30	5.20	5.25	0.15	11.81		
30	45		Cum	1	15.00	5.20	5.30	5.25	0.15	11.81		
45	60		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
60	75		Cum	1	15.00	5.30	5.40	5.35	0.15	12.04		
75	90		Cum	1	15.00	5.40	5.30	5.35	0.15	12.04		
90	105		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
105	120		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
120	121		Cum	1	1.00	5.10	5.10	5.10	0.15	0.77		
121	127		Cum	1	6.00	6.10	6.10	6.10	0.15	5.49		
		Cross Road 1 (W1185)										
		North to South										
0	15		Cum	1	15.00	5.30	5.30	5.30	0.15	11.93		
15	20.5		Cum	1	5.50	5.30	5.30	5.30	0.15	4.37		
20.5	24.5		Cum	1	4.00	2.50	2.50	2.50	0.15	1.50		
		Cross Road 2 (W1193)										
		North to South										
0	15		Cum	1	15.00	5.35	5.40	5.38	0.15	12.09		
15	28		Cum	1	13.00	5.40	4.80	5.10	0.15	9.95		
		Cross Road 3 (W1197)										
		North to South										
0	15		Cum	1	15.00	4.50	5.15	4.83	0.15	10.86		
15	18.6		Cum	1	3.60	5.15	5.15	5.15	0.15	2.78		
18.6	23.5		Cum	1	4.90	3.40	3.40	3.40	0.15	2.50		
23.5	27		Cum	1	3.50	5.15	5.10	5.13	0.15	2.69		
		Cross Road 4 (W1201)										
		North to South										
0	8.8		Cum	1	8.80	5.95	6.00	5.98	0.15	7.89		
8.8	15		Cum	1	6.20	4.30	5.10	4.70	0.15	4.37		
15	27.3		Cum	1	12.30	5.10	4.90	5.00	0.15	9.23		
		Cross Road 5 (W1183)										
		North to South										
0	15		Cum	1	15.00	5.10	5.00	5.05	0.15	11.36		
15	30		Cum	1	15.00	5.00	5.00	5.00	0.15	11.25		
30	34		Cum	1	4.00	5.00	4.90	4.95	0.15	2.97		
		R A Store Oppo Road (W0966)										
		East to West										
0	15		Cum	1	15.00	3.60	3.80	3.70	0.15	8.33		
15	24.5		Cum	1	9.50	3.80	3.90	3.85	0.15	5.49		
		Sameer Salon Road (W1425)										
		South to North										
0	4.2		Cum	1	4.20	3.60	3.60	3.60	0.15	2.27		
4.2	15		Cum	1	10.80	2.60	3.30	2.95	0.15	4.78		
15	30		Cum	1	15.00	3.30	3.60	3.45	0.15	7.76		
30	45		Cum	1	15.00	3.60	3.70	3.65	0.15	8.21		
45	60		Cum	1	15.00	3.70	3.80	3.75	0.15	8.44		
60	62.2		Cum	1	2.20	3.80	3.80	3.80	0.15	1.25		
62.2	63.4	Culvert	Cum	1	0.00	3.80	5.30	4.55	0.15	0.00		
63.4	67		Cum	1	3.60	3.80	3.80	3.80	0.15	2.05		
67	80		Cum	1	13.00	3.80	4.00	3.90	0.15	7.61		
80	95		Cum	1	15.00	4.00	3.90	3.95	0.15	8.89		
95	110		Cum	1	15.00	3.90	3.70	3.80	0.15	8.55		

Scanned by CamScanner

110	125		Cum	1	15.00	3.70	3.90	3.80	0.15	8.55		
125	129		Cum	1	4.00	3.90	3.90	3.90	0.15	2.34		
		M.S Pharma Oppo. Road (W1441)										
		North to South										
0	15		Cum	1	15.00	3.80	3.40	3.60	0.15	8.10		
15	30		Cum	1	15.00	3.40	3.80	3.60	0.15	8.10		
30	45		Cum	1	15.00	3.80	3.80	3.80	0.15	8.55		
45	53.1		Cum	1	8.10	3.80	3.80	3.80	0.15	4.62		
		Cross Road 1 (W0982)										
		East to West										
0	15		Cum	1	15.00	3.70	3.60	3.65	0.15	8.21		
15	30		Cum	1	15.00	3.60	3.60	3.60	0.15	8.10		
30	42.9		Cum	1	12.90	3.60	3.80	3.70	0.15	7.16		
		Cross Road 2 (W0978)										
		East to West										
0	15		Cum	1	15.00	3.40	3.40	3.40	0.15	7.65		
15	23.1		Cum	1	8.10	3.40	3.40	3.40	0.15	4.13		
23.1	28.7		Cum	1	5.60	1.90	1.90	1.90	0.15	1.60		
		Inspire Public School Oppo. Road (W0990)										
		West to East										
0	15		Cum	1	15.00	3.90	4.60	4.25	0.15	9.56		
15	20		Cum	1	5.00	4.60	4.85	4.73	0.15	3.54		
		Cross Road 4 (W0984)										
		East to West										
0	15		Cum	1	15.00	4.80	4.90	4.85	0.15	10.91		
15	19.5		Cum	1	4.50	4.90	5.00	4.95	0.15	3.34		
		Cross Road 3 (W0984)										
		West to East										
0	15		Cum	1	15.00	4.35	4.20	4.28	0.15	9.62		
15	24.9		Cum	1	9.90	4.20	4.20	4.20	0.15	6.24		
		Cross Road 2 (W0980)										
		East to West										
0	13.9		Cum	1	13.90	4.50	4.50	4.50	0.15	9.38		
13.9	18.6		Cum	1	4.70	4.00	4.00	4.00	0.15	2.82		
18.6	20.3		Cum	1	1.70	2.60	2.60	2.60	0.15	0.66		
20.3	25.4		Cum	1	5.10	3.30	3.30	3.30	0.15	2.52		
		Cross Road 1 (W0980)										
		West to East										
0	15		Cum	1	15.00	4.90	4.90	4.90	0.15	11.03		
15	24.1		Cum	1	9.10	4.90	4.90	4.90	0.15	6.69		
		Masjid-E-Uqba Road (W1483)										
		North to South										
0	8		Cum	1	8.00	5.00	4.30	4.65	0.15	5.58		
8	20		Cum	1	12.00	3.65	3.70	3.68	0.15	6.62		
20	30.5		Cum	1	10.50	3.70	3.90	3.80	0.15	5.99		
30.5	45		Cum	1	14.50	3.00	4.40	3.70	0.15	8.05		
45	50		Cum	1	5.00	4.40	4.80	4.60	0.15	3.45		
50	62.1		Cum	1	12.10	3.80	3.85	3.83	0.15	6.94		
62.1	67.1		Cum	1	5.00	5.00	4.95	4.98	0.15	3.73		
67.1	80		Cum	1	12.90	4.70	6.15	5.43	0.15	10.50		
80	95		Cum	1	15.00	6.15	6.10	6.13	0.15	13.78		
95	110		Cum	1	15.00	6.10	5.35	5.73	0.15	12.88		
110	125		Cum	1	15.00	5.35	4.80	5.08	0.15	11.42		
125	140		Cum	1	15.00	4.80	4.70	4.75	0.15	10.69		
140	141.2		Cum	1	1.20	4.70	4.70	4.70	0.15	0.85		
		Railway Under Bridge										
0	26		Cum	1	26.00	4.90	4.90	4.90	0.15	19.11		
		Bharath Store (W1411)										
		North to South										
0	15		Cum	1	15.00	5.15	5.35	5.25	0.15	11.81		
15	30		Cum	1	15.00	3.80	5.10	4.45	0.15	10.01		
30	45		Cum	1	15.00	5.10	5.30	5.20	0.15	11.70		
45	60		Cum	1	15.00	5.30	5.10	5.20	0.15	11.70		
60	75		Cum	1	15.00	5.10	5.40	5.25	0.15	11.81		

Scanned by CamScanner

75	88.4		Cum	1	13.40	5.40	5.55	5.48	0.15	11.00		
									Total Executed Quantity	**1012.42**	**6500.00**	**6580709.00**
									Tender Quantity	**1012.72**		
E1		KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 P.NO 23 I NO 5.6										
		Amara Jyothi Layout Main Road										
		2nd Cross Road										
			Cum	2	5.50	0.45	0.45	0.45	0.60	2.97		
		3rd Cross Road	Cum	2	6.10	0.45	0.45	0.45	0.60	3.29		
		4th Cross Road	Cum	2	6.90	0.45	0.45	0.45	0.60	3.73		
		6th Cross Road	Cum	2	4.40	0.45	0.45	0.45	0.60	2.38		
		7th Cross Road	Cum	2	6.20	0.45	0.45	0.45	0.60	3.35		
		8th Cross Road	Cum	2	5.75	0.45	0.45	0.45	0.60	3.11		
									Total Executed Quantity	**18.82**	**5113.89**	**96239.00**
E2		KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4. (P.No-27,I No-5.26.2) solid concrete blocks of size 400x150x200mm										
		W1515										
0	15		Sqm	2	15.00				0.20	6.00		
15	30		Sqm	2	15.00				0.20	6.00		
30	39.3		Sqm	2	9.30				0.20	3.72		
									Total Executed Quantity	**15.72**	**1028.12**	**16163.00**
											Sub Total	**45901335.00**
											For 12% Applicable GST	**5508161.00**
											Total Amount	**51409496.00**

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Technical sanction
Accepted for Rs. 51409496.00
Premium of 6% P.38'23
GER.NO : 23 Dt. 31.07.2022

Scanned by CamScanner